

JUL 24 1987

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED

MAR 5 9 25 AM '97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
BARRY
(County)

Located In: Corner Code #

1. Public Land Survey CORNER COMMON TO SECTIONS 25 & 36 ON RANGE LINE MAPLE GROVE TOWNSHIP	T	2N	R	7W	M-11
2. Property Controlling in Section	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	

Sandy ...
REGISTER OF DEEDS

002476

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **BRIAN REYNOLDS**, in a field survey on **OCTOBER 9**, 19**96**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE DEPUTY SURVEYOR JOHN MULLETT, 1825, SUG 7 S19W 3 LYNN 10 N42W 62
- CORRESPONDING CLOSING CORNER WAS ESTABLISHED BY GENERAL LAND OFFICE DEPUTY SURVEYOR MUSGROVE EVANS, 1826. EVANS REPORTED THE CLOSING CORNER TO BE 23 LINKS (15.18 FEET) SOUTH OF M-9.
- CORNER IS NOT RECITED IN BARRY COUNTY SURVEYOR RECORDS.
- PRIVATE NOTES OF DON DAVIS, PS #17817, c. 1973, REFERRING TO THE CORRESPONDING CLOSING CORNER, "NW CORNER 5/8" IRON 18.05' S OF BARRY" UTILITY POLE N50°E 31.03' 12" MAPLE S85°W 60.29' 5" MAPLE S20°E 71.75'
- LAND CORNER RECORDATION CERTIFICATE #462 BY DOUGLAS W. BONNEMA, PS #12579, RECORDED SEPT 14, 1992, "FOUND 1/2" SOLID ROD ON C/L GRAVEL N & S AND 2' S OF C/L GRAVEL TO W. SET NAIL IN S SDE P. POLE TO E 24.97' SET NAIL IN W SDE 12" MAPLE S-SE 89.69' SET NAIL IN N SIDE 22" MAPLE W-SW 64.72' SET NAIL IN W SDE 10" MAPLE N-NE 161.75'

ACCEPTED 1/2" SOLID ROD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON AND ALL OF BONNEMA'S WITNESSES FROM ITEM 5 ABOVE. FOUND ALL OF DAVIS' WITNESSES, BUT NO IRON FOR CLOSING CORNER; HOWEVER POSITION RESTORED FROM WITNESSES FIT WITH DAVIS' CALL FOR 18.05' S OF BARRY. EXCAVATED WITH BACKHOE AN AREA 20' N-S BY 10' E-W TO A DEPTH OF 4+ FEET IN SEARCH OF OTHER MONUMENTATION FOR BOTH STANDARD AND CLOSING CORNERS, FOUND NUMEROUS PIECES OF WHITE AND RED BRICK SCATTERED OVER A WIDE AREA NORTH-SOUTH, APPARENTLY DISTRIBUTED BY A ROAD GRADER. DID NOT FIND ANY STONE REPRESENTING EITHER STANDARD OR CLOSING CORNER; HOWEVER ABOUT ONE FOOT SOUTH OF IRON RECORDED BY BONNEMA, FOUND TWO LARGE PIECES OF UNDISTURBED BRICK IN CLAY BELOW GRAVEL ROAD. BASED ON TRAVERSE OF 2 1/2 MILES OF RANGE LINE FROM M-13 TO M-8, AND FOUND UNDISTURBED BRICK, ACCEPTED CORNER POSITION RECORDED BY BONNEMA AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

10-14-96

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)
- FOUND PK NAIL IN THE S. SIDE OF UTILITY POLE S88°E 24.99'
- FOUND NAIL IN THE W. SIDE OF 12" MAPLE S10°E 89.69'
- FOUND NAIL IN THE N. SIDE OF 24" MAPLE S71°W 64.69'
- SET 20d NAIL W/REMON TAG IN THE E. SIDE OF 30" TWIN WALNUT S16°W 81.95'
- A-11 T2N R6W (EATON COUNTY REMON IRON) SOUTH 18.05'
- APPROXIMATELY ON CENTERLINE OF GRAVEL ROAD N-S (CURTIS ROAD)
- APPROXIMATELY ON CENTERLINE OF GRAVEL ROAD W (EVART ROAD)



Signed by *Brian Reynolds*

Date FEB 18, 1997

Surveyor's Michigan License No. 31602