

SURVEY & REMONUMENTATION

JUL 24 1997

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
RECORDED BY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 5 9 25 AM '97

Sandy J. ...
REGISTER OF DEEDS

For corners in **BARRY**

(County)

Located In: Corner Code #

1. Public Land Survey	T	2N	R	7W	M-12
EAST 1/4 CORNER SECTION	T		R		
36 MAPLE GROVE TOWNSHIP	T		R		
ON TOWNSHIP LINE	T		R		
2. Property Controlling in Section	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	

002477

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **BRIAN REYNOLDS**, in a field survey on **OCTOBER 9**, 19 **96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE DEPUTY SURVEYOR JOHN MULLETT, 1825, (R7W, P.46) BEECH & S75W 14 IRONWOOD 6 N55 1/2W 14**
- CORNER IS NOT RECITED IN RECORDS OF THE BARRY COUNTY SURVEYOR. CORRESPONDING CLOSING CORNER IS NOT RECITED IN THE RECORDS OF THE EATON COUNTY SURVEYOR.**
- PRIVATE NOTES OF DON DAVIS, P.S. #17617, WHILE WORKING IN SECTION 31 OF KALAMO, IN HIS WITNESSES FOR A-13 OF KALAMO HE RECITES "9.24' SOUTH OF BARRY COUNTY IRON."**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOTH IRONS RECITED BY DAVIS AND MOST WITNESSES FOR CORRESPONDING CLOSING CORNER. EXCAVATED WITH BACKHOE AN AREA 6'X20' TO A DEPTH OF 3+FEET SEARCHING FOR OTHER EVIDENCE OF MONUMENTATION, FOUND NOTHING. AFTER TRAVERSING 2 1/2 MILES OF RANGE LINE, TYING IN ALL CORNERS FROM M-13 TO M-8, ACCEPTED IRONS RECITED BY DAVIS AS BEST EVIDENCE OF BOTH THE STANDARD AND CLOSING CORNERS.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

10-19-96
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)**
- SET 20d NAIL W/REMON TAG IN THE S. SIDE OF 12" MAPLE CLUSTER S47°E 26.52'**
- SET 20d NAIL W/REMON TAG IN THE W. SIDE OF 24" MAPLE S15°E 78.25'**
- SET CHISELED "X" IN TOP CENTER OF 14"X14" CONCRETE PILLAR S65°E 23.30'**
- SET 1/2" CAPPED IRON "REYNOLDS 31602" S33°W 36.15'**
- SET 1/2" CAPPED IRON "REYNOLDS 31602" N66°W 18.81'**
- A-12 T2N R6W (EATON COUNTY REMON IRON) SOUTH 9.24'**



Signed by

Brian Reynolds

Date

FEB 18, 1997

Surveyor's Michigan License No.

31602