

FEB 03 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For Corners in BARRY Located In: Corner Code #
(county)

1. Public Land Survey T 2N R 8W
WEST ¼ CORNER T _____ R _____
SECTION 30 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____

A-10



2743
Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCROR

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 13 JULY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- CORNER NOT SET BY GENERAL LAND OFFICE SURVEY.
- NO RECORD OF THIS CORNER CAN BE FOUND IN THE COUNTY SURVEYOR RECORDS:

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO DIRECT EVIDENCE OF CORNER MONUMENTATION. FOUND A CORNER FENCE POST AT APPARENT A-10, T2N R8W ALONG THE NORTHEAST SIDE OF TRAIL ROAD RUNNING NW-SE. SEARCHED IN BRIARS AND HEAVY UNDERBRUSH WEST OF TRAIL ROAD, FOUND TRACES OF FENCE THAT, IF PROJECTED EAST, WOULD INTERSECT APPARENT RANGE LINE 5'+/- SOUTH OF FOUND CORNER FENCE POST. THE GOVERNMENT JOG AT M-9 IS NORTH, 9.24' FROM STANDARD TO CLOSING CORNER; THE GOVERNMENT JOG AT M-11 IS ZERO, AS THIS IS A COMMON CORNER. THUS THE MEAN OF THE GOVERNMENT JOGS WOULD BE 4.62'. ACCEPTED THE FOUND FENCE POST AS BEST AVAILABLE EVIDENCE OF THE LOCATION OF A-10, T2N R8W, SET M-10 4.62 FEET SOUTH OF A-10 AND ON RANGE LINE.
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 20" BEECH N90°E 8.84'
- SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 20" CHERRY S15°E 64.10'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 20" MAPLE S44°W 35.00'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 30" MAPLE S84°W 53.00'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 30" MAPLE N52°W 36.60'
- M-10, T2N, R9W, BARRY COUNTY MONUMENT LIES SOUTH 4.62'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 July 98
BRIAN REYNOLDS

RR
COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date DEC 15, 1998