

BARRY COUNTY REMONUMENTATION

FEB 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located in: _____ Corner Code # _____
(county)

1. Public Land Survey T 2N R 8W B-10
CENTER OF SECTION 30 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____
T _____ R _____

 **2739**
Page: 1 of 1
12/17/1998 12:35P
Sandy Schonelmayr - Barry Co. LGRCR

Register of Deeds Stamp & File Number

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	●	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 13 JULY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.

*** NO HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. FOUND FENCE CORNER WITH STANDING FENCES RUNNING WEST AND SOUTH AND DECAYING FENCES RUNNING NORTH AND EAST. EXCAVATION AT BASE OF FENCE CORNER REVEALED NOTHING. FENCE CORNER LIES ON LINE BETWEEN REESTABLISHED A-10 & REESTABLISHED C-10, AND 0.91' WEST OF LINE BETWEEN REESTABLISHED B-9 & FOUND B-11.
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT WITH ALUMINUM CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 36" OAK S26°W 8.93'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF AN 8" BEECH S12°E 43.73'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF AN 8" OAK S76°E 40.98'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF AN 8" OAK N50°E 46.96'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 30" MAPLE N02°E 38.69'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 July 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date DECEMBER 15, 1998