

BARRY COUNTY REMONUMENTATION

FEB 03 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: Corner Code #
(county)

1. Public Land Survey T 2N R 8W B-11
1/4 CORNER COMMON TO T _____ R _____
SECTIONS 30 & 31 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____



2738
Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 13 JULY, '98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P.84) Be. 12 N57E 17 BOXWOOD 4 N65W 17
 - PRIVATE NOTES OF ROBERT R. CARR, P.S. #20704, 3-16-1982 (JOB # 8247) "1/2" IRON" 4" IRON FENCE POST SOUTH 33.0' U-POLE N5°E 62.17' 6" TWIN MAPLE S65°E 27.65'

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" IRON BY CARR AND ALL WITNESSES (NO NAILS). AFTER COMPLETE TRAVERSE OF SECTION 30, ACCEPTED FOUND 1/2" IRON BY CARR AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 20" WALNUT N58°E 40.26'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 24" WALNUT N19°E 30.43'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 14" MAPLE N70°W 76.68'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 10" ASH S67°W 35.54'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 12" TWIN MAPLE S45°E 27.82'
CORNER LIES ROUGHLY EAST-WEST GRAVEL CENTERLINE
4" IRON FENCE CORNER POST S01°E 33.01'**

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
13 July 98
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date DEC 15, 1998