

SURVEY & REMONUMENTATION

BARRY COUNTY REMONUMENTATION

SEP 14 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: _____ Corner Code # _____
(county)



2611
Page: 1 of 1
09/16/1997 11:49A

Sandy Schondelmayer - Barry Co. LCRCR

- 1. Public Land Survey T 2N R 8W C-1
- CORNER COMMON TO T _____ R _____
- SECTIONS 5 & 6 T _____ R _____
- BALTIMORE TOWNSHIP T _____ R _____
- ON TOWNSHIP LINE
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number _____

- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____

A	B	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1				
3										
4	7	8	9	10	11	12				
5										
6	18	17	16	15	14	13				
7										
8	19	20	21	22	23	24				
9										
10	30	29	28	27	26	25				
11										
12	31	32	33	34	35	36				
13										

I, **Brian Reynolds**, in a field survey on **16 MAY, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P.84) "NORTH BOUNDARY 28. E. OF POST. SET POST FOR CORNER OF 5.6" W. OAK 24 S32W 39 BE. 12 S49E 60
- 2. COUNTY SURVEYOR RECORDS: A.D. RORK, MARCH, 1866(L.1,P.246) "BEARINGS FOUND"
- 3. ALSO: BOWEN, MAY 1878(L.1,P.246) "POST BY U.S. BEARINGS"
- 4. COUNTY ROAD COMMISSION: "WOODEN STAKE 19.4' E. OF SE COR. 31-3-8
- 5. LAND CORNER RECORDATION CERTIFICATE: #240, BY ROBERT R. CARR, P.S.#20704, NOVEMBER 1976, "FOUND R.R. SPIKE SET BY ROY DeHAVEN R.L.S. 3380, 19.4' EAST OF SOUTHEAST COR. SEC. 31 TOWN 3 NORTH, RANGE 8 WEST" APPROX CENTERLINE ROAD E&W EAST SIDE BITUMINOUS PAVEMENT NORTH UTILITY POLE S45°W 85.20' 30" OAK S45°E 43.00' 19.35' EAST OF SE COR SEC. 31 TOWN 3 NORTH, RANGE 8 WEST
- 6. PRIVATE NOTES OF R. GERTZ, OCTOBER, 1976, "RAILROAD SPIKE" APPROX CENTERLINE ROAD E&W EAST SIDE OF PAVEMENT NORTH U.POLE S45°W 85.20' 30" OAK S45°E 43.00' 19.35' EAST OF SE COR. SEC. 31 T3N, R8W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE AND ALL OF GERTZ AND CARR'S WITNESSES.
EXCAVATION REVEALED NO FURTHER EVIDENCE.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
REPLACED FOUND RAILROAD SPIKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP IN MONUMENT BOX.

- FOUND NAIL IN THE EAST SIDE OF A 48" OAK S45°E 44.88'
- SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 48" QUAD OAK S7°E 152.53'
- SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 24" WALNUT S9°W 120.75'
- SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 22" WALNUT S7°W 138.57'
- SET "PK" IN THE NORTH SIDE OF A UTILITY POLE S52°W 85.54'
- C-13 T3N, R8W LIES N89°42'33"W 19.33'
- CORNER LIES ON EAST-WEST-SOUTH CENTERLINES

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 May, 96 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date 9/15/97