

SURVEY & REMONUMENTATION

FEB 0 9 1999

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: Corner Code #
(county)

- 1. Public Land Survey T 2N R 8W C-10
 1/4 CORNER COMMON TO T _____ R _____
 SECTIONS 29 & 30 T _____ R _____
 BALTIMORE TOWNSHIP T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____



2736
Page: 1 of 1
12/17/1998 12:35P
Sandy Schondelmayer - Barry Co. LCRGR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 13 JULY 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S. 1826 (R8W, P.80) B. ASH S71W 4 Be. 8 N84E 17
 - COUNTY SURVEYOR RECORDS: SETH PRATT, 16-17 APRIL, 1883 (L.2, P. 227) SUGAR 16 N52 1/2 W 31 BEECH 6 N88 1/2 W 59 1/4 STUB B. ASH 6 S71W 4

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. FOUND FENCE LINE RUNNING NORTH AND SOUTH ONLY. AFTER COMPLETE TRAVERSE OF SECTION 30, TYING IN OCCUPATION LINES, PROJECTED LINE FROM RESTORED A-10 THROUGH SUBSTANTIAL FENCE CORNER AT B-10 TO INTERSECT NORTH-SOUTH FENCE. FROM CORNER POSITION THUS DETERMINED TO:

C-11 S00°31'38"W, 2656.42'
 C-9 N00°01'31"W, 2645.95'
 B-10 N89°12'40"W, 2684.93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
 SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 6" MAPLE CLUSTER S34°E 25.31'
 SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 14" MAPLE S17°E 35.75'
 SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 14" OAK S32°W 47.55'
 SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 14" ELM N22°W 18.47'
 SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF AN 18" CHERRY N15°W 69.49'
 CORNER LIES 25'+/- SOUTH OF AN INTERMITTENT EAST-WEST STREAM

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 July 98
BRIAN REYNOLDS
COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date DECEMBER 15, 1998