

**SURVEY &  
REMONUMENTATION**

FEB 17 1998



Sandy Schondelmayer - Barry Co. LCRCR

**2631**

Page: 1 of 1  
12/16/1997 12:15P

**SECTION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

<b>For Corners in BARRY COUNTY</b>	<b>Located In:</b>	<b>Corner Code #</b>
1. Public Land Survey S1/4 COR COMMON TO SEC. 32 BALTIMORE TWP.	T..2N R..8W T..... R..... T..... R..... T..... R.....	....D-13.... ..... ..... .....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....	..... .....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....	..... .....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RAYMOND MOORED, in a field survey on OCTOBER 5, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. J. MULLETT, D.S. 1826; SET POST; W. OAK 16 N191/2W 62, Y. OAK 18 N43E 64.  
POWER LINE SURVEY BY CONS. POWER CO., CIRCA 1950, CORNER IS WOOD STAKE AND STONE.  
MISC. WITNESSES 3/4" IRON FOR CORNER; 25' WEST OF JOHNSTOWN CORNER; P. POLE S75E 18.85';  
14" BOX ELDER S60W 49.8' ( NO NAME OR DATE )  
NO OTHER HISTORICAL DATA AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
MEASURED FROM STATIONING ON OLD CONS. POWER CO. POLE LINE SURVEY ALONG N & S  
1/4 LINES OF SEC 32 BALTIMORE AND SEC. 5 JOHNSTOWN. DUG AT APPROXIMATE INTERSECTION  
OF TOWN LINE AND 1/4 LINES AND FOUND LARGE FLAT STONE IN PIT OF STONES FOR JOHNSTOWN CORNER.  
SET D-13 25' WEST OF D-1, JOHNSTOWN ON LINE BETWEEN D-1 AND C-1 OF JOHNSTOWN.

SET BARRY COUNTY REMONUMENTATION IRON W/ CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 13 May, '96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL IN NW SIDE POWER POLE S75W 19.55'  
-NAIL IN N SIDE 12" BEECH S45W 61.00'  
-NAIL IN N SIDE 6" BEECH N85E 74.03'  
-IN LINE WITH OCCUPATION LINE TO NORTH AND WEST  
-NORTH 1/4 COR (D-1), T1N, R8W EAST 25.00'

Signed by Raymond Moored  
Surveyor's Michigan License No. 26463

Date 12/11/97

