

SURVEY & REMONUMENTATION

JUL 24 1997

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN COUNTY OF BARRY REGISTERED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MAR 5 9 26 AM '97

For corners in BARRY (County)

Located In: Corner Code #

1. Public Land Survey CENTER OF SECTION 4 BALTIMORE TOWNSHIP

T 2N R 8W

F-2

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Sand... REGISTER OF DEEDS

002490

Register of Deeds Stamp & File Number

BRIAN REYNOLDS

6 MAY

96

I, in a field survey on 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. THIS CORNER NOT SET BY THE GENERAL LAND OFFICE.
2. RECORDED PLAT OF CAPPON'S COUNTRY ACRES, BY Wm. HUME ROGERS, P.S. #6197, 1966, CORNER WAS REFERENCED, NO WITNESSES GIVEN.


NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO PHYSICAL EVIDENCE OF CORNER MONUMENTATION. FOUND INTERSECTION OF NORTH-SOUTH-EAST-WEST FENCES TO BE 8' SOUTH AND 5' EAST OF TRUE INTERSECTION OF 1/4 LINES. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES.

Grid table with columns A-M and rows 1-13. A black dot is located at the intersection of column F and row 2.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 5-13-96 BRIAN REYNOLDS COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)
SET A RING OF LARGE AND SMALL STONES AROUND MONUMENT
SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 24" OAK S14°E 22.74'
SET 20d NAIL W/REMON TAG IN THE EAST ROOT OF A 20" OAK S8°E 14.59'
SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A 10" CHERRY S15°W 7.37'
SET 20d NAIL W/REMON TAG IN THE NORTHEAST SIDE OF A 10" MAPLE S66°W 21.53'
FOUND 60d NAIL IN THE NORTH SIDE OF A 22" OAK N78°W 37.70'
CORNER LIES 8'+/- NORTH OF AN EAST-WEST FENCE AND 5'+/- WEST OF A NORTH-SOUTH FENCE

Signed by [Signature]

Date FEB 18 1997