

**SURVEY &  
REMONUMENTATION**

JUL 24 1997

COMMISSION

**BARRY COUNTY REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BARRY COUNTY  
RECORDED

17 JUN 97 12:21 P.M.

SANDY SCHONDELMAYER  
REGISTER OF DEEDS

**002508**

Register of Deeds Stamp & File Number

For Corners in BARRY Located In: Corner Code #  
(county)

1. Public Land Survey T 2N R 8W Corner Code # F-3  
1/4 CORNER COMMON TO T \_\_\_\_\_ R \_\_\_\_\_  
SECTIONS 4 & 9 T \_\_\_\_\_ R \_\_\_\_\_  
BALTIMORE TOWNSHIP T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **Brian Reynolds**, in a field survey on **10 DECEMBER, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W,P.78) WEST CORRECTED 39.93  
A. B. OAK 14 N51E 38 BOXWOOD 6 N35W 10 LINKS
- LAND CORNER RECORDATION CERTIFICATE: #333, BY ROBERT R. CARR, P.S. #20704, 1981, "FOUND REMAINS OF OLD FENCE RUNNING E. & W., TRAVERSED OCCUPATION OF N. & S. 1/4 LINES OF SECTIONS 9 & 4 AND SET CORNER AT LOCATION ESTABLISHED FROM OCCUPATION."  
1/2" IRON 18" ASH S85°W 12.0' 10" OAK S30°E 31.8' 6" BASSWOOD N60°E 7.0'

\*\*\* NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF CORNER MONUMENTATION OR WITNESSES BY CARR (ITEM #2 ABOVE), BELIEVE WITNESSES TO BE FOR ANOTHER CORNER.

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF FENCES.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL IN THE NORTH SIDE OF A 10" MAPLE S80°E 36.44'
- SET 20d NAIL IN THE NORTH SIDE OF AN 18" OAK S70°W 85.79'
- SET 20d NAIL IN THE WEST SIDE OF A 12" OAK N15°E 49.10'
- FOUND NAIL IN THE SOUTH SIDE OF A 4" ELM WEST 21.60'
- IN NORTH-SOUTH FENCE IN EAST-WEST FENCE

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

5-13-96  
BRIAN REYNOLDS

BR  
COUNTY SURVEYOR



Signed by

Surveyor's Michigan License No 31602

Date

MAY 16, 1997