

DEC 7 2 40 PM '93

Sandy Schindelmarper
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry County
(County)
Baltimore Township

Located In: Corner Code #
T 2N R 8W F-11
T _____ R _____ (1/4 Cor. Common
T _____ R _____ to Sections 28
T _____ R _____ and 30)
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

002108

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth C. Brandt, in a field survey on September 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 14" W. Ash N.13° E. 17 L.
3" Hickory S. 4 1/2° E. 16 L
County Road Comm. found stone - SE cor. HSE N.20° W. 68.1' 6" tree N.45° W. 53.1'
(1973) R. Gertz found nail over Iron 1' + ' E. of Fence to North
NW Cor. Conc. Block Gar. S.45° E. 49.70
NE Cor. Conc. Block Gar. S.70° E. 68.0

SURVEY &
REMONUMENTATION

APR 05 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

COMMISSION

Found 1/2 Rebar in Mon. Box
NW Cor Conc. Block Gar. - S.45° E. 49.81'
NE Cor. Conc. Block Gar. - S. 70° E. 68.12'
Fence to North 2' + W. of Iron stake
In center line of Bituminous roadway.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" rebar and replaced with 3/4" Iron pin & aluminum Remon. cap with punch mark in mon. box.
Nail & Barry County remon. shiners set as follows:
S. side 30" Maple N.75° W. 124.69 feet
E. side 14" Elm N.10° E. 42.36 feet
SE side 10" Maple N.45° E. 70.37 feet
NW corner Conc. Block Garage S.45° E. 49.81'

Signed by Kenneth C. Brandt

Date 11/5/93

Surveyor's Michigan License No. 24587