

SURVEY & REMONUMENTATION

JUL 24 1997

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

002509

For Corners in BARRY (county)

Located In: _____ Corner Code # _____

1. Public Land Survey T 2N R 8W G-2
 1/4 CORNER COMMON TO SECTIONS 3 & 4
 BALTIMORE TOWNSHIP
 ON TOWNSHIP LINE
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec.
 S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
BARRY COUNTY
RECORDED
17 JUN 97 12:21 P.M.
SANDY SCHONDELMAYER
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Brian Reynolds**, in a field survey on **7 SEPTEMBER, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W,P.74)
COUNTY SURVEYOR RECORDS: LEE S. COBB, 1898 (L.2,P.287) "FOUND STUB OF ONE U.S. BEARING TREE MARKS & LETTERS PLAIN ORIG. TAMK 6 EAST 13 LKS" "SET OAK STAKE & STONES"
B. ASH 8 N36°E 5 1/2 LKS B. ASH S4°E 28 1/4 LKS

*** NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NO EVIDENCE OF CORNER MONUMENTATION. FOUND OLD DECAYING FENCE LINES RUNNING NORTH, SOUTH, & WEST IN A LARGE WOODED SWAMP.
ACCEPTED INTERSECTION OF FENCES AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
CORNER LIES IN THE EAST EDGE OF A HUMMOCK/ROOT SYSTEM, ON THE WEST SIDE OF THE ROOTS OF AN UPROOTED TREE.

SET 5' LONG BUGGY AXLE WITH BARRY COUNTY REMONUMENTATION CAP ON TOP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 5' LONG BUGGY AXLE WITH BARRY COUNTY REMONUMENTATION ALUMINUM CAP ON TOP (IN SWAMP)
SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 6" ELM N89°W 1.44'
SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 6" ELM N31°W 8.65'
SET 20d NAIL W/REMON TAG IN THE NORTHEAST SIDE OF A 6" ELM N60°W 11.33'
SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 4" ELM N29°W 11.92'
IN LINE WITH A DECAYED FENCE RUNNING WEST
0.5 FEET EAST OF A DECAYED FENCE LINE RUNNING NORTH AND SOUTH

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
 5-13-96
 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by Brian Reynolds
 Surveyor's Michigan License No. 31602

Date MAY 16, 1997