

DEC 7 2 40 PM '93

Sandy Schindelmayr
 REGISTER OF DEEDS

002109

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry County

Located In: Corner Code =#

(County)
Baltimore Township

- | | | |
|------------------------------------|-------------------------|----------------------------|
| 1. Public Land Survey | T <u>2N</u> R <u>8W</u> | <u>G-5</u> |
| | T _____ R _____ | (Section corner |
| | T _____ R _____ | common to Sections |
| | T _____ R _____ | <u>9, 10, 15 & 16)</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth C. Brandt, in a field survey on September 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 6" Ironwood N.30° E. 10L.
 10" " S.48° W. 28E.

County surveyor Bowen (1876 found stone & stake, Witnesses gone).
 EXXEL Engineering (L.C.R.C. #215 7/15/77) Set 1/2" Iron pipe on & of pavement with fence lines North and South.

Nail in side 12" Walnut South 32.40'
 Nail in side 12" Willow NE 70.54'
 Nail in side 8" Elm NW 76.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron pipe in center of pavement, on fence line to South.

Nail in side 12" Willow NE 70.54
 Nail in side 8" Elm NW 76.32



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" Iron pipe and replaced with 3/4" Iron pin with Aluminum Barry County Remon. cap. with punch mark:
 Set nail and Barry County Remon. shiners as follows:
 SW side of 16" Elm N.45° W. 76.35'
 NW side of 15" Willow N.45° E. 70.64'
 NE side of 3" Hickory S.50° E. 81.04'
 E side of 4" Hickory S.20° W. 35.35'

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION

Signed by Kenneth C. Brandt

Date 11/3/93

Surveyor's Michigan License No. 24587