

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

SECTION

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 2N R 8W H-12
CENTER 1/4 CORNER T _____ R _____
SECTION 34 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____



2859
Page: 1 of 1
12/27/1999 01:44P

Darla K. Burghdoff - Barry Co. LCRCR

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	●	35	36							
13													

I, Brian Reynolds, in a field survey on 8 NOVEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
2. COUNTY SURVEYOR RECORDS: LEE S. COBB, 5 APRIL, 1910 (L.1, P. 371) "SET 1/4" GAS PIPE" ELM 8 S55 1/2E 9

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER POSITION. CORNER LIES IN AN EXCAVATED TRAIL RUNNING NORTHWEST TO SOUTHEAST. THE ADJOINING LAND OWNER ON THE NORTHWEST SIDE (DUANE JONES) TELLS US THAT HE ONCE OWNED THE ADJOINING LAND TO THE SOUTHEAST. HE BULL DOZED A TRAIL ACROSS THE CENTER OF SECTION IN ORDER TO OPEN A TRAIL FOR FARM EQUIPMENT. TIED IN FENCE LOCATION NORTH, SOUTH, EAST AND WEST, AND CORNER OCCUPATION 1/4 MILE EAST AND WEST. INTERSECTION OF 1/4 LINES IS CONSISTENT WITH FENCE OCCUPATION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A RAILROAD TIE FENCE POST S06°W 12.37'
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 30" MAPLE N85°E 14.82'
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF AN 8" OAK S63°W 47.81'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 4" OAK S21°W 34.77'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 12" OAK S40°E 55.19'
- CORNER LIES 1.5' EAST OF FENCE LINE TO THE SOUTH
- CORNER LIES 5'± NORTH OF IRREGULAR FENCE LINE RUNNING EAST



ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Nov. '99
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

Signed by [Signature]
Surveyor's Michigan License No 31602

Date DEC 27, 1999