

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

SECTION

For Corners in
BARRY
(county)

Located in: Corner Code #

1. Public Land Survey
CORNER COMMON TO
SECTIONS 26, 27, 34 & 35
BALTIMORE TOWNSHIP

T 2N R 8W 1-11
T _____ R _____
T _____ R _____
T _____ R _____



2818
Page: 1 of 1
12/07/1999 08:36A

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 8 NOVEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P. 64) Be. 24 S30W 20 Do. 10 N11E 25
 - COUNTY SURVEYOR RECORDS: LEE S. COBB, 5 APRIL, 1910 (L. 1, P. 371) "FOUND STONE IN PLACE"
SUGAR 2 S36 1/4E 60 1/2LKS CHERRY 8 S52W 78LKS

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ON EAST-WEST CENTERLINE. CHERRY WITNESS BY COBB IS GONE, BUT THE MAPLE, S36 1/4E 60 1/2 LINKS (39.93') STILL STANDS. CORNER LIES IN A 5'+ FILL AREA AND AN EXCAVATION WOULD NOT BE PRACTICAL. ACCEPTED FOUND IRON AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP IN MONUMENT BOX.

- SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A 16" OAK N31°E 44.08'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 36" MAPLE S14°W 69.65'
- FOUND NAIL W/METAL TAG IN THE EAST SIDE OF A 32" OAK N10°E 24.45'
- FOUND NAIL W/METAL TAG IN THE SOUTHEAST SIDE OF A 30" MAPLE S36°E 39.26'
- CORNER LIES ON EAST-WEST PAINTED CENTERLINE
- CORNER LIES 2± EAST OF CENTERLINE TO THE SOUTH



ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Nov. '99
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

Signed by *Brian Reynolds*
Surveyor's Michigan License No 31602

Date Dec 3, 1999
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971