

BARRY COUNTY REMONUMENTATION

SURVEY &
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 04 2000

SECTION

For Corners in BARRY Located In: Corner Code #
(county)

1. Public Land Survey T 2N R 8W 1-12
1/4 CORNER COMMON TO T _____ R _____
SECTIONS 34 & 35 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____



2860
Page: 1 of 1
12/27/1999 01:44P

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 8 OCTOBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P. 64) Be. 6 S50E 9 SUGAR 12 S54W 3
- COUNTY SURVEYOR RECORDS: LEE S. COBB, 5 APRIL 1910 (L.1, P.371) "FOUND 1/2" GAS PIPE" BEECH 12 N54 1/2E 43 LYNN 7 N75 1/2W 24

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE 1 1/2' BELOW GRAVEL ROAD GRADE. LYNN WITNESS BY COBB (ITEM #2 ABOVE) IS NOW A 20" TRIPLE (BITTERNUT). MEASURED BEARING AND DISTANCE TO THE NORTHERNMOST TRUNK, N75°W 15.80'. COBB RECITES N75W 24 LINKS (15.84').
ACCEPTED FOUND PIPE AS PERPETUATION OF CORNER POSITION BY COBB.
REPLACED FOUND PIPE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A 14" CHERRY N29°E 47.83'
SET 20d NAIL W/REMON TAG IN THE SOUTH TRUNK OF A TRIPLE 18" BUTTERNUT N73°W 15.63'
FOUND NAIL WITH METAL TAG IN THE SOUTH TRUNK (OVERGROWN) OF A TRIPLE 18" BUTTERNUT N73°W 15.24'
SET 20d NAIL W/REMON TAG IN THE SOUTHEAST SIDE OF AN 8" MAPLE S40W 31.77'
TOP CENTER OF A 3" STEEL FENCE ANCHOR POST N85°E 23.07'
CORNER LIES ON THE WEST EDGE OF A NORTH-SOUTH GRAVEL ROAD
CORNER LIES 2± SOUTH OF FENCE LINE RUNNING EAST

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Nov. '99
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date DEC 27, 1999