

DEC 7 2 40 PM '93

Sandy Schondelmar  
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry County  
(County)  
Baltimore Township

Located In: Corner Code #

1. Public Land Survey

T2N R8W K-3

T \_\_\_ R \_\_\_ (Sec. cor. common  
to Sections 1, 2,  
11 & 12)

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

002110

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth C. Brandt in a field survey on September 6 19 93  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 24" Beech S.46° E. 45 L  
20" Poplar N.34° W. 53 L

County Surveyor. Bowen (1876) set stake, stone 30" x 18" x 12" Crockery & Brick.  
Pratt, Willson, Bowen (L. 1. P. 197) Reset cor. stake, large stone & plow point.  
Pratt found cor. (1889) all above witnesses gone. County Road Comm. found stone and brick  
1971, set Iron Stake (only witness found was anchor post 23.4 West)  
Wm. H. Rogers found 3/4" pipe, stone and brick per LCRC #17 (1972) found anchor post 23.4'  
West and old stump S.45° E. 41.07'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe - only witness found was anchor post 23.4' West of 3/4" pipe.

SURVEY &  
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 3/4" pipe and replaced with 3/4" Iron pin with Aluminum Remon. Cap with punch mark 1"  
below pavement surface - 2' N. of fence to West 4' S. of center line of North-South pavement  
and 4' S. of center line of Gravel road to East.

Nail & Barry County remon. shiners set as follows:

NE side of 24" Walnut - N. 40° W. 51.62'  
NW side of 24" Hickory - N. 25° E. 78.59'  
N. side of 24" Walnut S.75° E. 92.35'  
SE side of 14" Elm S.40° W. 35.01'

Signed by Kenneth C. Brandt

Date 11/5/93

Surveyor's Michigan License No. 24587

