

BARRY COUNTY REMONUMENTATION

RECORDATION & DEEDS DIVISION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 04 2000

For Corners in
BARRY
(county)

Located In: Corner Code #

SECTION

1. Public Land Survey
¼ CORNER COMMON TO
SECTIONS 11 & 12
BALTIMORE TOWNSHIP

T 2N R 8W K-4
T _____ R _____
T _____ R _____
T _____ R _____



2777
Page: 1 of 1
06/21/1999 02:12P

Sandy Schondelmayer - Barry Co. LCRCR

2. Property Controlling in Section
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Brian Reynolds, in a field survey on 19 AUGUST, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P.63) SUGAR 12 S43E 5 ELM 21 N38W 21
2. COUNTY SURVEYOR RECORDS: FRANK BOWEN, MARCH 1876 (L.1, P.151) "SET STAKE STONE 18"X10"X18" PLOW POINT & BRICK" WALNUT 10 SW 98 B. OAK 9 NW 95
3. COUNTY SURVEYOR RECORDS: FRANK BOWEN, SETH PRATT & A.C. WILLSON, MAY 1877 (L.1, P.197) "SET STAKE STONE PLOW POINT & BRICK" WALNUT 10 SW 98 B. OAK 9 NW 95
4. COUNTY ROAD COMMISSION: NO NAME OR DATE (#583 CHARLTON PK. RD. F.B. P. 2) "SET BRIDGE SPIKE =00°00'46"LT" 6" OAK N75E 66.9' 8" WALNUT S40°W 40.9' 34" OAK N45W 40.55'

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. FOUND NO WITNESSES FROM PART "A" ABOVE. TRAVERSED ALL OF SECTIONS 1, 12 & 13 TYING IN OCCUPATION. ESTABLISHED POSITION AT THE MID POINT AND ON LINE BETWEEN K-3 & K-5. EXCAVATION AT THE MID POINT REVEALED NOTHING, BUT IS CONSISTENT WITH 1/8 LINE OCCUPATION NORTH, SOUTH & EAST. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 40" ASH S80°W 64.15'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 30" MAPLE S82°W 106.16'
INSCRIBED "X" ON TOP OF THE SOUTHEAST CORNER TELEPHONE RISER N49°E 47.65'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE S64°E 173.18'
CORNER LIES 2'+/- EAST OF NORTH-SOUTH CENTERLINE
CORNER LIES 3'+/- SOUTH OF EAST-WEST CENTERLINE


ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 JUNE 1998

BR

BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date JUNE 21, 1999