

**BARRY COUNTY REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

APR 04 2000

For Corners in BARRY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(county)

SECTION \_\_\_\_\_

1. Public Land Survey T 2N R 8W L-1  
NORTH ¼ CORNER T \_\_\_\_\_ R \_\_\_\_\_  
SECTION 1 T \_\_\_\_\_ R \_\_\_\_\_  
BALTIMORE TOWNSHIP T \_\_\_\_\_ R \_\_\_\_\_  
ON TOWNSHIP LINE
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_



**2787**

Page: 1 of 1  
11/16/1999 09:00A

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 14 AUGUST, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
- COUNTY SURVEYOR RECORDS: SETH PRATT, MARCH 1889 (L-2, P.265) "FOUND BY U.S. BEARING. PLACED POST 10 ½ LKS. EAST OF HASTINGS POST. MADE NEW BEARING" TAMARACK 18 N35 ½ W 21 ½ LKS DEAD
- LAND CORNER RECORDATION CERTIFICATE: #238 BY MILTON E. DEKEYSER, P.S. #12019, 10 JUNE, 1975, "FOUND TILE AT FENCE CORNER W/ FENCE WEST, SOUTH AND SOUTHEAST (APPARENTLY SET IN RESURVEY, 1826)" NO WITNESSES GIVEN
- PRIVATE NOTES: FROM THE DEKEYSER FILES, P. McPHERESON, JUNE 1975, "TILE W/IRON IN FENCE CORNER. IN FENCE CORNER WITH FENCE SOUTH WEST & SOUTHEAST"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. FOUND FENCE CORNER IN SWAMP WITH DECAYING FENCES RUNNING EAST-WEST-SOUTHEAST AND 12'± WEST OF A BADLY DECAYING FENCE TO THE NORTH. EXTENSIVE EXCAVATION REVEALED NO EVIDENCE OF TILE OR IRON AS RECITED BY DEKEYSER OR McPHERESON (ITEMS 3 & 4 ABOVE). TRAVERSED ALL OF SECTION 1, TYING OCCUPATION. FENCE CORNER IS ABOUT 2 FEET WEST OF MID-POINT BETWEEN K-1 AND M-1, AND ABOUT 8 FEET NORTH OF A DIRECT LINE. ACCEPTED FOUND FENCE CORNER AS BEST AVAILABLE EVIDENCE OF POSITION OF TILE AND IRON RECITED BY DeKEYSER. SET STANDARD BARRY COUNTY MONUMENT AND CAP AT FENCE CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.  
SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 20" WILLOW N37°E 34.80'  
SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 4" ELM S69°E 68.10'  
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 10" POPLAR S34°E 82.38'  
SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 10" POPLAR S27°E 51.98'  
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 12" WILLOW S26°W 80.48'  
CORNER LIES AT THE INTERSECTION OF DECAYING FENCES RUNNING SOUTHEAST / EAST / WEST  
L-13, T3N, R8W, LIES WEST 6.93'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 June '98  
BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by

*[Signature]*

Date

11/15/1998