

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

SECTION _____

1. Public Land Survey T 2N R 8W _____ M-4
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
4. Lot No _____, Recorded Plat _____
5. Private Claims _____



2790
Page: 1 of 1
11/16/1999 09:00A

Daria K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 8 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, Brian Reynolds, in a field survey on 10 AUGUST, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1826 (R8W, P. 52)
 2. COUNTY SURVEYOR RECORDS: FRANK BOWEN, 26-27 JUNE 1878 (L. 1, P. 248) "FOUND OLD CORNER, POST & BRICK" SUG 18, S72W 19 BEECH 6 N20W 24
 3. PRIVATE SURVEY OF METES AND BOUNDS PARCEL IN SECTIONS 6 & 7, T2N R7W BY BRIAN REYNOLDS, P.S. #31602, JUNE 1992 FOUND FENCE CORNER AT APPARENT M-4 T2N R8W, SET 1/2" CAPPED IRON AT PRORATED GOVERNMENT JOG FOR A-4, T2N R7W. NOT WITNESSED.
 4. PRIVATE NOTES OF SURVEY OF METES AND BOUNDS PARCEL IN SECTION 12 PROVIDED BY RAYMOND MOORED, P.S. #26463, MONUMENT AND WITNESSES NOT PROVIDED.

***** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ****

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND FENCE CORNER AND CAPPED IRON AS DESCRIBED IN ITEM #3 ABOVE. EXCAVATION AROUND FENCE CORNER REVEALED NO EVIDENCE OF MONUMENTATION. FROM SECTION MEASUREMENTS PROVIDED BY MOORED, IT APPEARED THAT MOORED HAD USED THE IRON INTENDED FOR A-4 AS THE CORNER FOR M-4. CONVERSATION WITH MOORED CONFIRMED THIS. MOORED STATED THAT HIS TIE WAS TO ESTABLISH RANGE LINE ONLY, AND THAT THE DIFFERENCE WOULD MAKE NO DIFFERENCE FOR HIS SURVEY. TRAVERSED RANGE LINE FROM M-1 TO M-7, FOUND THAT AVERAGE STANDARD HALF-MILE MEASURED 2653.5'. MEASURED DISTANCE FROM FENCE CORNER AT M-4 TO M-3 2656.56'; FROM FENCE CORNER AT M-4 TO M-5 2651.91'. ACCEPTED FENCE CORNER AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY MONUMENT AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
FOUND NAIL W/CAP IN THE TOP CENTER OF A RAILROAD TIE CORNER POST EAST 0.50'
FOUND NAIL W/CAP IN A 24" MAPLE N28°E 31.05'
FOUND NAIL W/CAP IN A 16" MAPLE N30°W 24.42'
FOUND NAIL W/CAP IN A 10" MAPLE N44°E 18.06'
A-4, T2N, R7W, LIES NORTH 12.80'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 June '98 
BRIAN REYNOLDS COUNTY SURVEYOR

Signed by 
Surveyor's Michigan License No 31602

Date 11/15/1999

