

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 04 2000

SECTION

For Corners in BARRY (county) Located In: Corner Code #

1. Public Land Survey CORNER COMMON TO SECTIONS 12 & 13 BALTIMORE TOWNSHIP ON RANGE LINE T 2N R 8W M-5
2. Property Controlling in Section S T R
3. Miscellaneous S T R



2791 Page: 1 of 1 11/16/1999 09:00A

Darla K. Burghdoff- Barry Co. LCROR

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Brian Reynolds, in a field survey on 14 AUGUST, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13 for section identification

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P.52) BEECH 12 S48W 68 Do. 6 N52W 41
2. COUNTY SURVEYOR RECORDS: FRANK S. BOWEN, JUNE 1878 (L.1, P.249) "FOUND ONE BEARING & STAKE, SET STAKE"
3. PRIVATE NOTES: SURVEY BY RAY MOORED, P.S. #26463, c. 1995 "FOUND IRON FOR M-4, T2N, R8W, IN MON BOX, SET IRON FOR A-4, T2N, R7W, 12.54' NORTH"
4. COUNTY ROAD COMMISSION: DON WOLF, 1996 "SET MONUMENT BOX"

**** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ****

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN MONUMENT BOX 4' +/- NORTH OF CENTERLINE OF BITUMINOUS ROAD (LAWRENCE ROAD). ALSO FOUND IRON 12.54' NORTH, OFF ROAD SURFACE, NEAR GUARD RAIL. IT APPEARED THAT THE MONUMENT IN THE MONUMENT BOX WAS TO REPRESENT M-5, T2N R8W; THAT THE IRON TO THE NORTH WAS TO REPRESENT A-5, T2N R7W. TRAVERSED RANGE LINE FROM M-1 TO M-7, FOUND THAT AVERAGE STANDARD HALF-MILE MEASURED 2653.5'. FROM THE MEASUREMENTS ALONG RANGE LINE, THE IRON FOUND BY MOORED MORE LIKELY REPRESENTED A-5. CONVERSATION WITH MOORED CONFIRMED THAT THE IRON HE FOUND IN THE MONUMENT BOX WAS USED AS A-5, THAT THE POSITION FOR M-5 WAS COMPUTED TO BE SOUTH OF THE FOUND IRON, BUT THAT THE FIELD CREW HAD SET THE CORRESPONDING CORNER IN THE WRONG DIRECTION. ACCEPTED FOUND IRON IN MONUMENT BOX AS A-5, T2N R7W. SET STANDARD BARRY COUNTY MONUMENT AND MONUMENT BOX 12.54 FEET SOUTH OF FOUND IRON IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 5" MAPLE N42°W 65.93' SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 5" MAPLE N03°E 45.83' SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 24" MAPLE S08°E 45.98' SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 10" MAPLE S48°W 44.78' CORNER LIES 8'+/- SOUTH OF EAST-WEST CENTERLINE IN LINE WITH FENCES NORTH-SOUTH A-5, T2N, R7W, LIES NORTH 12.54'

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 June '98 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature] Surveyor's Michigan License No. 31602

Date 11/15/1999