

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

SECTION _____

1. Public Land Survey T 2N R 8W M-6
EAST 1/4 CORNER T _____ R _____
SECTION 13 T _____ R _____
BALTIMORE TOWNSHIP T _____ R _____
ON RANGE LINE

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____



2792

Page: 1 of 1
11/18/1999 09:00A

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 19 AUGUST, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1826 (R8W, P.52) TAMK. 7 S59 1/2W 48 W. OAK 8 N3W 91

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND INTERSECTION OF FENCES NORTH, SOUTH, EAST, WEST, AT THE MARGIN OF A SMALL SWAMP WITHOUT ANY APPARENT NORTH-SOUTH JOG AS WOULD BE EXPECTED ALONG THE RANGE LINE. FENCE TO NORTH AND WEST IS A NEWER HIGH-TENSILE FENCE, APPARENTLY RUN TO THE EXISTING OLDER FENCE TO THE EAST. EXTENSIVE EXCAVATION AT FENCE CORNER AND 6.5 LINKS NORTH AND SOUTH OF FENCE CORNER, AND ALL OF THE AREA BETWEEN, REVEALED NO EVIDENCE OF MONUMENTATION. TRAVERSED RANGE LINE FROM M-1 TO M-9, TYING IN CORNERS AND OCCUPATION. SUBSEQUENT ANALYSIS OF MEASUREMENTS REVEALED THAT FENCE CORNER MOST PROBABLY REPRESENTS CLOSING CORNER A-6, T2N R8W. PLACED A-6 ON RANGE LINE AT FENCE CORNER, PLACED M-6 ON RANGE LINE 6.5 LINKS (4.29') SOUTH OF A-6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A FENCE CORNER POST S85°E 9.04'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 16" WILLOW S55°E 36.69'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 12" MAPLE S80°E 26.65'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 10" WILLOW N45°E 14.40'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 12" SOFT MAPLE N15°E 31.65'
CORNER IS IN LINE WITH FENCE NORTH
4'± SOUTH OF EAST-WEST FENCE
A-6, T2N, R8W, MAPLE GROVE TOWNSHIP LIES NORTH 4.29'



ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

10 Aug 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR

Signed by [Signature]
Surveyor's Michigan License No. 31602

Date 11/15/1999