

APR 08 1996

BARRY COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

OCT 16 10 59 AM '95

Sandy Schondelmarer
REGISTER OF DEEDS

002299

Register of Deeds Stamp & File Number

For corners in

<u>Barry</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>9W</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

HOPE TOWNSHIP

I, William K. Crane, in a field survey on January 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Government Land Office: Sylvester Sibley D.S. 1827 (R. 9 W. P. 91)

intersected West boundary 62 links South of Post.

A.W. Oak 12" N 39 E 19 links
D.O. 7" S 57 E 53 links

A.D. Rork December 1865 L.2 P.58 found bearings.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found traces of old fence South, extended centerline of East and West road to intersect fence South. Excavated at this intersection and found remains of large corner wooden fence post. Accepted this as best evidence of corner position. Traverse of occupation in area shows this fits well with computed position for this corner.


ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9 OCT. '95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Barry County Remonumentation Monument with aluminum cap.

Set nail w/cap 10" Hickory S 76° E 53.50'
Set nail w/cap 6" Oak S 19° E 36.48'
Set nail w/cap 12" Oak N 73° W 4.94'
Set nail w/cap 18" Twin Oak N 16° W 54.56'



Signed by William K. Crane Date October 9, 1995
Surveyor's Michigan License No. 29243