

MAY 20 1997

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED

DEC 9 2 10 PM '96

Sandy Schindlman REGISTER OF DEEDS

For corners in

Form with fields: BARRY (County), Located In, Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec.

002433

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, RAYMOND MOORED, in a field survey on MAY, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

COUNTY ROAD COMMISSION (MILLER RD. 1960, P.2 BICKNELL) FOUND IRON 6" HICKORY N60DEG. W. 26.0' 8" HICKORY N. 40DEG. W. 38.5' 6" HICKORY S. 35DEG. E. 46.5' STAKE E. 8' SEC. COR.?

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DETERMINED EXISTING IRON TO BE E. 1/4 POST SEC. 36 ORANGEVILLE. SET W. 1/4 POST SECTION 31 AT 1/2 GOV'T JOG AT N.W. CORNER

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 10 April, '95 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY CO. REMON IRON W/CAP -E 1/4 POST SEC. 36 ORANGEVILLE SOUTH 2.97' -PK & TAG S. SIDE P. POLE S 85DEG.W. 14.22' -PK & TAG NE SIDE 8" HICKORY S 28DEG E. 36.25' -PK & TAG SW SIDE 8" HICKORY S 35DEG. E. 35.20' -PK & TAG NW SIDE 28" RED OAK N 50DEG E. 64.17'



Signed by Raymond Moored Surveyor's Michigan License No. 26463

Date 11/4/96