

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED

Dec 9 2 10 PM '96

Sandy Schindelmarer
REGISTER OF DEEDS

002434

Register of Deeds Stamp & File Number

For corners in BARRY (County)	Located in:	Corner Code #
1. Public Land Survey N1/4 COR. TO SEC. 31 HOPE TWP.	T 2N R 9W	B-11
2. Property Controlling in Section	T R	
3. Miscellaneous Property in Sec.	T R	
	S T R	
	S T R	
	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11	●												
12	31		32		33		34		35		36		
13													

I, RAYMOND MOORED, in a field survey on MARCH, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. S. SIBLEY D.S. 1827 (R9W,P.86). W. WOOD 14 N20E 22; W. ASH 6 S7E 23. COUNTY SURVEYOR RECORDS COBB 11-9-1912 (BROWN HOPE TWP FIELD BOOK PG 15 BEYOND GLO TRANS) FD STUMP OF US TREE WHITEWOOD AND STONE, BEECH 16 N7W 20LKS; W ASH 10 N75E 3 1/2 LKS BATEMAN JUNE 1899, L.1, PG 336- ONE GOV'T WITNESS STANDING WITNESSED A 10" BEECH N9W 14' RECORDED SURVEY BY JENSEN (P.S. # 31593) 11-27-90 REC IN L.2, PG. 10- IRON IN WOODS, NO OCCUPATION; 8" BEECH SOUTH 5'; 20" BEECH S50W 21'; 16" BEECH NORTH 45.5'; 6" BEECH N35E 15.2'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN WOODS PER RECORDED SURVEY BY JENSEN; WITNESSES REMAIN. ACCEPTED FOUND IRON AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
10 April, '95
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-P.K. IN EAST SIDE 16" BEECH NORTH 45.05'
-P.K. IN SE SIDE 8" BEECH N50°E 14.97'
-P.K. IN WEST SIDE 10 BEECH SOUTH 5.00'
-P.K. IN SE SIDE 22" BEECH S 70°W 20.55'
-CENTERLINE OF NORTH- SOUTH TRAIL WEST 6' +/-



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 11/4/96