

Survey of
REMONUMENTATION

MAY 20 1997

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY BARRY
RECEIVED

DEC 9 2 10 PM '96

Sandy Schondelmar
REGISTER OF DEEDS

For corners in
BARRY
(County)

Located In:	Corner Code #
1. Public Land Survey CORNER COMMON TO SEC. 32 HOPE TWP.	T <u>2N</u> R <u>9W</u> <u>D-13</u>
2. Property Controlling in Section	T _____ R _____
3. Miscellaneous Property in Sec.	T _____ R _____
	S _____ T _____ R _____
	S _____ T _____ R _____
	S _____ T _____ R _____

002439

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RAYMOND MOORED, in a field survey on MAY, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. JOHN MULLETT D.S. 1826 (R9W, P.53) B. ASH 7 N. 71 W. 41. BEECH 6. N. 54 E. 36. COUNTY SURVEYOR RECORDS BATEMAN 6 APRIL 1900 (L.1, P. 348) FOUND GOV'T WITNESS (ASH) N. 34 E. 8' BEECH 34 1/2 FT. N 34 W. 14' HICK 36 FT. B. 12 S 38 1/4 E. 43 1/2. PRATT (BROWN HOPE TWP. F.B, P.5 BEYOND GLO TRANSCRIPTIONS GOV BEARING GREEN NEW BEARING BEECH 12 S. 38 1/4 E. 43 1/2 (TAN BARRY TWP. F.B, P.15) ASH 7 N 71 W. 41 B 6 N. 54 E. 36.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF CORNER LOCATION SET CORNER ON TOWN LINE 142.56 FEET WEST OF N 1/4 CORNER SEC. 5 BARRY TWP. AS PREVIOUSLY LOCATED BY HEATH. ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION SET STANDARD BARRY COUNTY REMON IRON W/CAP.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
9 OCT '95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMON IRON W/CAP
-NAIL IN NE SIDE 4" ELM N45DEG W. 1.28'
-NAIL IN NW SIDE 6" BIRCH N50DEG. E. 16.98'
-NAIL IN N SIDE 10" HICKORY S 60DEG. E. 14.86'
-NAIL IN E SIDE 12" HICKORY SOUTH 21.60'
-CENTERLINE BRICKYARD ROAD NORTH 60' +



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 11/4/96