

**SURVEY &  
REMONUMENTATION**

FEB 17 1998

SECTION



**2635**

Page: 1 of 1  
12/16/1997 12:15P

Sandy Schondelmayer - Barry Co. LCRCR

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in BARRY CO.	Located In:	Corner Code #
1. Public Land Survey SEC COR COMMON SEC. 9 & 16 HOPE TWP.	T..2N R..9W T..... R..... T..... R..... T..... R.....	...F-5..... ..... ..... .....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....	..... .....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....	..... .....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on SEPT. 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO. S. SIBLEY, D.S., 1827 WEST CORRECTED 39.97 SET QR SEC. POST  
W. ASH 7 N1W 9; HICKORY 7 S681/2E 15  
COUNTY SURVEYOR RECORDS: BOWEN 1876, L.1, PG. 140;  
HICKORY 8 S49E 86; W. OAK 14 N10E 1.21 1/2  
COUNTY ROAD COMM. - STONE, 18" ASH N45E 36.7'; 20" ASH N20E 57.1'; 12" WILLOW N45W 42.8'  
UNRECORDED LCRC BY R. CARR, P.S. DATED 21 APRIL, 1982 - 3/4" IRON  
18" ASH N65E 64.1'; 16" HICKORY N20W 76.0'; 16" OAK S50W 77.1'  
REFERENCED BY PLAT OF HINEWOOD, LIBER 3 OF PLATS, PAGE 69.  
REFERENCED BY PLAT OF WESTVIEW, LIBER 5 OF PLATS, PAGE 66.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 3/4" IRON PER UNRECORDED LCRC BY CARR; 16" HICKORY REMAINED. REMOVED IRON AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 18 Nov '96 *RR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
- NAIL & TAG IN E SIDE 18" HICKORY N20W 76.15'
- NAIL & TAG IN E SIDE FENCE CORNER POST N45W 55.70'
- NAIL & TAG IN W SIDE FENCE CORNER POST N40E 51.78'
- NAIL & TAG IN W SIDE 30" WALNUT N50E 63.88'

Signed by Raymond Moored

Date 12/11/97

Surveyor's Michigan License No. 26463

