

REMONUMENTATION

APR 08 1996

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 15 3 07 PM '95

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmarer
REGISTER OF DEEDS

For corners in
BARRY
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>2N</u>	<u>R9W</u>	<u>J-6</u>
CENTER OF SECTION 14	T		R	
HOPE TOWNSHIP	T		R	
	T		R	
2. Property Controlling	S		R	
in Section	S		R	
3. Miscellaneous	S		R	
Property in Sec.	S		R	

002362

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, BRIAN REYNOLDS, in a field survey on 9 MARCH, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER NOT SET BY GENERAL LAND OFFICE.
COUNTY SURVEYOR RECORDS: JOHN CRESSY, 2-3 MARCH, 1874(L.1,P.24)
ELM 14 N33 3/4W 37 CHERRY 10 S38W 36 1/2

NOTE: MINUTES OF SURVEY BY CRESSY REFER TO THE EAST 1/4 CORNER WITH THE FOLLOWING:
"STONE IN ROAD. THIS IS DOUBTFUL CORNER. A FEW OF THE SETTLERS THINK IT IS RIGHT & I HAVE ALLOWED IT TO REMAIN FOR THE PRESENT. I THINK IT IS WRONG. SHOULD BE SET SOUTH 31 lks WEST 15 (MARGINAL NOTE 9) lks TO BE AT EQUAL DISTANCE AND ON TRUE LINE."

NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND INTERSECTION OF FENCES, OLD WOVEN WIRE FENCE SOUTH MOSTLY STILL STANDING, FENCE WEST ENTIRELY DOWN, OLD WOODEN FENCE CORNER POST LEANING SOMEWHAT TO NORTHEAST EXCAVATED AROUND FENCE POST, FOUND SEVERAL SMALL STONES, NONE WITH MARKINGS. TIED IN EXTENSIVE OLD FENCE LINE OCCUPATION THROUGHOUT ENTIRE SECTION. MEASUREMENTS CONFIRM FENCE CORNER AS LOCATION OF CENTER OF SECTION AS DETERMINED BY CRESSY ACCEPTED FENCE CORNER AS BEST EVIDENCE OF CENTER OF SECTION 14 AS ESTABLISHED BY COUNTY SURVEYOR JOHN Q. CRESSY IN MARCH, 1874. SET STANDARD REMONUMENTATION MONUMENT 0.5 FEET NORTH OF CENTER OF WOODEN FENCE CORNER POST

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
13 March '95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 12" ELM N40°E 8.23'
SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF AN 18" OAK S35°E 17.21'
SET 40d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE, BASE, OF A 12" TRIPLE OAK S15°E 35.08'
CORNER LIES 0.5' NORTH OF THE CENTER OF A CORNER FENCE POST.
IN LINE WITH FENCE SOUTH AND DECAYED FENCE WEST.



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date 12/15/95