

STRAY &  
MONUMENTATION

APR 08 1996

COMMISSION

For corners in  
**BARRY**

(County)

**BARRY COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

DEC 15 3 07 PM '95

Sandy Schondelmayer  
REGISTER OF DEEDS

**002364**

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey <b>1/4 CORNER COMMON TO SECTIONS 13 &amp; 14 HOPE TOWNSHIP</b>	T <u>2N</u> R <u>9W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**BRIAN REYNOLDS** in a field survey on **9 MARCH**, 19**95**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

**GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1827(R9W,P.66) A W. OAK 20 N81E 15/A BEECH 9 N18W 19 COUNTY SURVEYOR: JOHN CRESSY, MAR., 1874(L.1,P.24)"STONE IN ROAD. THIS IS DOUBTFUL CORNER. A FEW OF THE SETTLERS THINK IT IS RIGHT & I HAVE ALLOWED IT TO REMAIN FOR THE PRESENT. I THINK IT IS WRONG. SHOULD BE SET SOUTH 31iks, WEST 15 (MARGINAL NOTE 9) Iks TO BE AT EQUAL DISTANCE & ON TRUE LINE"**

**ALSO: WALTER HEATH, OCT., 1903(L.3,P.90)"STONE 18"X12"X9" AND BRICK" MAPLE 10 S48 1/2W 26 3/4 BLACK OAK 18 N44 1/2E 71 1/2**

**NOTE: MINUTES OF HEATH SURVEY INDICATE CORNER WAS NOT FOUND; STONE WAS SET AT MID-POINT ON LINE BETWEEN K-5 AND K-7**

**SEE REVERSE OF THIS FORM FOR ADDITIONAL HISTORICAL DATA.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**FOUND 3/4" IRON IN MONUMENT BOX ON CENTERLINE OF BITUMINOUS ROAD.**

**CHECK OF WITNESSES INDICATES LOCATION OF FOUND IRON IS POSITION ESTABLISHED BY VAN KOOTEN IT SEEMS PROBABLE THAT THE POSITIONS NOTED IN PART "A" (AFTER GLO) REPRESENT FOUR DISTINCT LOCATIONS, THAT NO TWO LOCATIONS ARE COMMON. THE STATIONING AND WITNESSES RECITED BY THE ROAD COMMISSION INDICATE THAT CORNER WAS SET IN REFERENCE TO THE FENCE WEST, WHICH PROBABLY IS THE LINE BY CRESSY. TIES TO 1/8 CORNER 1/4 MILE EAST, AND CENTER OF SECTION 13 (BOTH BY HEATH) AND MEASUREMENTS TO K-5 AND K-7 INDICATE THE POSITION BY HEATH WOULD BE 2-3 FEET SOUTH OF THE FOUND IRON. EVIDENCE FROM MEASUREMENTS TO HEATH'S CORNERS IS CONFLICTING AS TO EAST-WEST POSITION RELATIVE TO FOUND IRON. DUE TO ROAD GRADING, IT IS HIGHLY IMPROBABLE THAT STONE BY HEATH CAN BE RECOVERED. ACCEPTED FOUND IRON AS BEST EVIDENCE OF CORNER POSITION, AFTER COMPLETE TRAVERSE OF SECTION 14 AND WEST 1/2 OF SECTION 13, WITH TIES TO HISTORICAL CORNERS PROVED FOUND IRON TO BE IN ACCEPTABLE POSITION REPLACED FOUND IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX.**


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)  
SET 40d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A UTILITY POLE N47°E 55.08'  
SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 30" OAK N15°E 96.39'(SAME TREE AS VAN KOOTEN)  
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF AN 18" OAK N15°W 101.220'  
SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 10" HICKORY N29°E 58.31'  
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S10°W 116.86'**

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 March '95  
**BRIAN REYNOLDS**  
COUNTY SURVEYOR

Signed by \_\_\_\_\_ Date 12/15/95  
Surveyor's Michigan License No. 31602



**CONTINUATION OF BLOCK "A"**

**ALSO: R.J. MERSHON (L.2,P.218) W. OAK 20 N21°50'W 2.72**

**COUNTY ROAD COMMISSION: CEDAR CREEK RD. #601, (F.B., P.2) 1957**

**STA. 81+93.5 SET BOAT SPIKE**

**4" TWIN HICKORY N45°E 36.3'**

**10" OAK N45°W 38.1'**

**8" OAK WEST 28.5'**

**LAND CORNER RECORDATION CERTIFICATE: #227 BY PAUL E. VAN KOOTEN SEPT., 1977**

**"SET 1/2" CAPPED IRON BY EXISTING PHYSICAL EVIDENCE"**

**NAIL IN 16" OAK W-NW 29.69'**

**NAIL IN 28" OAK N-NW 111.90'**

**NAIL IN 20" OAK N-NE 96.45'**

**NAIL IN 4" OAK E-NE 31.10'**

**NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.**