

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970.**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

DEC 14 8 54 AM '93

Sandy Schondelmar  
REGISTER OF DEEDS

**002174**

Register of Deeds Stamp & File Number

corners in  
BARRY  
(County)

Located In: Corner Code #/

Public Land Survey

T 2N R 9W K-8  
T \_\_\_\_\_ R \_\_\_\_\_ HOPE

Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

BRIAN REYNOLDS in a field survey on NOVEMBER 9TH, 19 93,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

CORNER ESTABLISHED BY G.L.O. DEPUTY SURVEYOR SYLVESTER SIBLEY UNDER CONTRACT  
DATED 5TH OCT., 1826. SET POST  
A BEECH 10 S57W 8  
A BEECH 6 N13W 10

REMONUMENTATION  
APR 05 1994  
COMMISSION

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" PIPE IN MON. BOX. REPLACED WITH STANDARD 3/4" REMONUMENTATION IRON  
AND ALUMINUM CAP.  
EXISTING CORNER IS S36°E 0.15 FEET FROM TRUE LOCATION APPEARS THAT CORNER WAS  
INTENDED TO BE HALF WAY AND ON LINE BETWEEN THE SW AND NW CORNERS OF THE SECTION.  
ACCEPTED THE FOUND 1/2" PIPE AS THE BEST AVAILABLE EVIDENCE OF THE CORNER POSITION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" REMONUMENTATION IRON WITH ALUM. CAP IN MON. BOX  
40D NAIL & WITNESS TAG IN NORTHEAST SIDE 20" OAK S65°E 77.81'  
40D NAIL & WITNESS TAG IN NORTH SIDE 12" OAK N76°E 39.36'  
40D NAIL & WITNESS TAG IN SOUTHEAST SIDE 16" FIR S26°W 67.39'  
40D NAIL & WITNESS TAG IN EAST SIDE 16" POPLAR N15°W 110.56'  
40D NAIL & WITNESS TAG IN NORTH SIDE 14" OAK N76°W 76.15'  
G. ROAD WEST 4.0'



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date DECEMBER 7, 1993