

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 14 8 54 AM '93

Sandy Schondelmayer
REGISTER OF DEEDS

002170

Register of Deeds Stamp & File Number

corners in
BARRY
(County)

Located In: Corner Code #

T	<u>2N</u>	R	<u>9W</u>	<u>L-9</u>
T	_____	R	_____	<u>HOPE</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

Public Land Survey

Property Controlling
in Section

Miscellaneous

Property in Sec.

Lot No. _____, Recorded Plat _____

Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

BRIAN REYNOLDS in a field survey on NOVEMBER 9TH, 19 93

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

CORNER ESTABLISHED BY G.L.O. DEPUTY SURVEYOR SYLVESTER SIBLEY UNDER CONTRACT DATED 5TH OCT., 1826. SET POST ON TRUE LINE AN IRONWOOD 7 S57E 25 AN IRONWOOD 6 N67W 16 SURVEY BY JIM KING, CO. SURVEYOR (FED. 1984) CORNER NOT RECORDED

SET 1/2" IRON
8" HICKORY S62°E 45.00'
12" TRIP. CHERRY N22°E 61.40'
20" HICKORY N21°W 82.10'
5' E & 4' N OF G

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON SET BY KING. MEASURED WEST 1327.4' TO 1/8 LINE OCCUP. AND 1319.6' TO SOUTHWEST CORNER. MEASURED SOUTH 1322.0 TO 1/8 LINE OCCUP. AND 1320.0 TO 1/4 LINE OCCUPATION. DISREGARDED KING'S CORNER AND SET 3/4" REMONUMENTATION IRON AND CAP AT DOUBLE THE 1/8 LINE DISTANCE FROM SOUTHWEST CORNER OF SEC. (2639.26') FURTHER COMPUTATIONS SHOWED THAT CENTER SET AT INTERSECT OF 1/4 LINES USING NEW S 1/4 CORNER FIT CENTER OCCUPATION AND OCCUPATION LINES 1/4 AND 1/2 MILE EAST AT EAST 1/4 CORNER. REMOVED KING'S 1/2" IRON.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" REMONUMENTATION IRON WITH ALUM. CAP.
40D NAIL & WITNESS TAG IN EAST SIDE 12" OAK S15°W 99.28'
40D NAIL & WITNESS TAG IN EAST TRUNK TRIP. BLACK WALNUT N77°E 97.22'
40D NAIL & WITNESS TAG IN NORTHWEST SIDE 10" HICKORY N65°E 52.33'
40D NAIL & WITNESS TAG IN EAST SIDE P. POLE N4°W 255.40'
TOP E. END 12" CMP ROAD CULVERT S10°E 186.50'
G₁ N-S GRAVEL RD. EAST 4.5'
G₂ E-W GRAVEL RD. SOUTH 3.5'



Surveyed by Brian Reynolds
Surveyor's Michigan License No. 31602

Date DECEMBER 7, 1993