

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 14 8 54 AM '93

Sandy Schondelmar
REGISTER OF DEEDS

002171

Register of Deeds Stamp & File Number

or corners in

BARRY
(County)

Located In: Corner Code #

Public Land Survey

T 2N R 9W M-7

T R HOPE

T R

T R

T R

Property Controlling
in Section

S T R

S T R

Miscellaneous

S T R

Property in Sec.

S T R

Lot No. Recorded Plat

Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

BRIAN REYNOLDS in a field survey on NOVEMBER 9TH, 19 93

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

CORNER ESTABLISHED BY G.L.O. DEPUTY SURVEYOR JOHN MULLETT UNDER CONTRACT DATED JANUARY 5, 1826. SET POST CORNER TO SECTIONS 13 AND 24
BEECH 9 S31 1/2W 64
MAPLE 14 N24W 55
SURVEY BY CO. SURVEYOR WALTER HEATH OCT. 13-19, 1903 FOUND STAKE BY BEARINGS OF RESURVEY ON SECTION 24 AND SET TRIANGULAR STONE FOR CORNER.
HICKORY 18 S0°-16E 26
MAPLE 7 N40 1/2E 1.09 1/2

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PROJECTED LINE FROM NORTHWEST CORNER OF SECTION THROUGH NORTH 1/8 POST, NORTHEAST 1/4 (FOUND GAS PIPE AS SET BY HEATH) AT PROPORTIONAL MEASURE TO HEATH'S DISTANCE. LOCATION ESTABLISHED FIT MEAS. SOUTH TO DEPRESSION IN GROUND AND REMNANTS OF OLD STUMP (HICKORY S0°-16E 26). DUG HOLE AND FOUND 8"x12" OBLONG STONE (FLAT ON TOP). DID NOT FIND ANY MARKINGS ON STONE AND DID NOT FIND ANY TRIANGULAR STONE IN HOLE. ACCEPTED LOCATION AND EVIDENCE AS BEST POSITION FOR CORNER AND SET 3/4" REMONUMENTATION IRON AND ALUM. CAP AT THIS LOCATION.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" REMONUMENTATION IRON AND ALUM. CAP
40D NAIL & WITNESS TAG IN SOUTHWEST SIDE 16" MAPLE N39°W 33.86'
40D NAIL & WITNESS TAG IN EAST SIDE 12" HICKORY NORTH 28.53'
40D NAIL & WITNESS TAG IN NORTH SIDE 18" HICKORY S86°E 25.93'
40D NAIL & WITNESS TAG IN SOUTHEAST SIDE 18" WALNUT S45°W 35.08'
40D NAIL & WITNESS TAG IN NORTH SIDE 28" WALNUT S74°W 81.89'
G. GRAVEL ROAD NORTH 12'



Signed by *Brian Reynolds*

Date DECEMBER 7, 1993

Surveyor's Michigan License No. 31602