

FEB 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located In: Corner Code #

1. Public Land Survey
EAST 1/4 CORNER
SECTION 25
HOPE TOWNSHIP
ON RANGE LINE

T 2N R 9W M-10
T _____ R _____
T _____ R _____
T _____ R _____



2757
Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling
in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 15 MAY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

- NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.
- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE DEPUTY SURVEYOR JOHN MULLETT, 1826, "W. OAK 16 SOUTH 55 ELM 7 N33 1/2 W 57"
 - NO RECORD OF THIS CORNER CAN BE FOUND IN THE COUNTY SURVEYOR RECORDS:

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO DIRECT EVIDENCE OF CORNER MONUMENTATION. FOUND A CORNER FENCE POST AT APPARENT A-10, T2N R8W ALONG THE NORTHEAST SIDE OF TRAIL ROAD RUNNING NW-SE. SEARCHED IN BRIARS AND HEAVY UNDERBRUSH WEST OF TRAIL ROAD, FOUND TRACES OF FENCE THAT, IF PROJECTED EAST, WOULD INTERSECT APPARENT RANGE LINE 5'+/- SOUTH OF FOUND CORNER FENCE POST. THE GOVERNMENT JOG AT M-9 IS NORTH, 9.24' FROM STANDARD TO CLOSING CORNER; THE GOVERNMENT JOG AT M-11 IS ZERO, AS THIS IS A COMMON CORNER. THUS THE MEAN OF THE GOVERNMENT JOGS WOULD BE 4.62'. ACCEPTED THE FOUND FENCE POST AS BEST AVAILABLE EVIDENCE OF THE LOCATION OF A-10, T2N R8W, SET M-10 4.62 FEET SOUTH OF A-10 AND ON RANGE LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 20" BEECH N74°E 8.73'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 20" CHERRY S14°E 59.61'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 20" MAPLE S58°W 32.49'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 30" MAPLE N80°W 53.55'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 30" MAPLE N36°W 40.33'
A-10, T2N, R8W, BARRY COUNTY MONUMENT LIES NORTH 4.62'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 July 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date Dec 15, 1998
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975 REVISED JANUARY, 1983 REVISED OCTOBER 1995