

SURVEY & REMONUMENTATION BARRY COUNTY REMONUMENTATION

FEB 0 8 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in SECTION Located In: Corner Code #
BARRY
(county)

1. Public Land Survey T 2N R 8W
CORNER COMMON TO T 2N R 9W
30 & 31 T2N R8W T _____ R _____
25 & 36 T2N R9W T _____ R _____
ON RANGE LINE
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____

A-11
M-11



2748
Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCRCR
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 13 JULY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

T2N R9W

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: M-11, T2N, R9W JOHN MULLETT, D.S., 1826 (R9W, P.54) BEECH 16 S23W 62 Do. 16 N25W 28
 - GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R8W, P.84) "WEST BOUNDARY AT THE POST"
Be. 5 S53 1/2 E 9 Do. 4 N62E 34
 - PRIVATE NOTES: BY ROBERT R. CARR, P.S. #20704, 3-16-82 (JOB # 8247) (WORKING IN SECTION 31, BALTIMORE TOWNSHIP) "SET 1/2" IRON" U. POLE S80E 117.88' 20" WALNUT S75W 88.21' 8" MAPLE S10E 27.79'
 - PRIVATE NOTES: BY GREGORY N. JENSEN, P.S., #31593, 11-22-91 (WORKING IN SECTION 25, HOPE TOWNSHIP) "FOUND 1/2" IRON" 10" W. O. NORTH 41.0' CL PP. S75°E 117.8' (CCPC 70 TAG) TRAV. CL. 2' SOUTH 9" WALNUT N45°W 57' CL.

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" IRON AS SET BY CARR & USED BY JENSEN. FOUND ALL WITNESSES AS RECITED IN #4 & #5 ABOVE (NO NAILS). AFTER COMPLETE TRAVERSE OF SECTIONS 19 & 30, AND A TIE TO THE SOUTHWEST CORNER OF 31 BALTIMORE, ACCEPTED FOUND 1/2" IRON AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. AS THE GENERAL LAND OFFICE RECITES THIS AS A COMMON CORNER TO M-11, T2N, R9W, HOPE TOWNSHIP, ACCEPTED FOUND 1/2" IRON AS A COMMON CORNER. REPLACED FOUND 1/2" IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 10" WALNUT S69°W 45.93'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 14" ASH S10°E 27.78'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 20" ASH N85°E 89.60'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 6" WALNUT N41°E 28.36'
CORNER IS IN LINE WITH TREE/FENCE LINE TO THE SOUTH, NO OCCUPATION TO THE NORTH
TRAVELED EAST-WEST GRAVEL CENTERLINE SOUTH 2'+/-

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
13 July 98
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date DEC 15, 1998