

DEC 7 4 26 PM '93

Sandy Schondelmarper

REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Barry</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>1N</u> R <u>8W</u>	<u>A-1</u>
	T <u>1N</u> R <u>9W</u>	<u>M-1</u>
	T <u>2N</u> R <u>9W</u>	<u>M-13</u>
	T <u>2N</u> R <u>8W</u>	<u>A-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

002136

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0: 10" Black Oak, N30°W, 10 links County Surveyor: F.B.#1, P.83
 8" Black Oak, S13°W, 25 links

County Road Commission:

Stone w/notch, small pointed stone on top.
 Iron fence post, S20°, 2 feet
 20" Maple, S30°E, 33.1 feet
 20" Basswood, S55°E, 55.1 feet

COBB: Found remains of stake & bearings

Set 21x19x12 stone & brick, S40½°E, 62½ links, this is a witness, not the corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron - searched for stone & brick, set by Cobb and also checked for stone with notch to verify the iron wasn't placed in error over Cobb's witness.
 Accepted this as a perpetuation of the true corner location as this has been used by others as the corner.

SURVEY &
 REMONUMENTATION

MAY 2 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" iron rod with aluminum remonumentation cap.
 34" Maple, S9°E, 33.75 feet. Found nail on West side.
 20" Maple, S43°E, 32.56 feet. Found P.K. on West side.
 14" Maple, N65°E, 30.51 feet. Nail & spotter on West side.
 20" Maple, S50°E, 41.47 feet. Nail in West side.



Signed by [Signature] Date September 8, 1993
 Surveyor's Michigan License No. 34975