

SURVEY & REMONUMENTATION



Sandy Schondelmayer - Barry Co. LCRCR

FEB 17 1998 **BARRY COUNTY REMONUMENTATION**
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in Located In: Corner Code #
BARRY CO.

1. Public Land Survey T..... R.....
 T..... R.....
 T..... R.....
 T..... R.....

HOPE TWP

2. Property Controlling S..16..T..2N..... R..9W... 12.....
in Section S.....T..... R.....

F-67

#3

3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **RAYMOND MOORED**, in a field survey on **SEPT. 10, 1996** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT ESTABLISHED BY GLO
CORNER REFERENCED ON PLAT OF "OAK HILL RESORT", LIB. 2 OF PLATS, PAGE 23 AND ON PLAT OF "HINWOOD", AS REC. IN LIBER 3 OF PLATS, PAGE 69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON BAR IN POSITION DELINEATED BY PLAT OF "OAK HILL RESORT"; REMOVED IRON AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 18 NOV, 96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN N SIDE 10" OAK S45W 53.76'
-NAIL & TAG IN W SIDE 42" WILLOW S30E 111.91'
-NAIL & TAG IN W SIDE 4" MULBERRY S2E 18.77'
-NAIL & TAG IN S SIDE FENCE CORNER POST N60W 113.97'

Signed by Raymond Moored

Date 12/11/97

Surveyor's Michigan License No. 26463

