

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>K-21</u> T. <u>T9N</u> N. R. <u>10</u> W.		<u>F-5, E-5, E-6, E-7, E-8</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
 FILING NUMBER _____

I, GA Shadko, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on _____, 1942, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-5 FOUND: FE. COR.
 E-5 FOUND: IRON ROD AT INTERSECT. OF FENCES
 E-6 FOUND POINTED STONE
 E-7 FOUND: old FENCE COR Post with stones AROUND IT
 E-8 FOUND 1 1/4" IRON ROD

NOTE: All witness distances GIVEN BELOW ARE to "V" NOTICES IN TREES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 Set Conc Mon. 8" ABOVE GR. Not wit.
 E-5 Set Conc Mon. 3" ABOVE GR. Not wit.
 E-6 Set Conc Mon. 8" ABOVE GR. Elm 26" N. 60° W. 14.0' E. 18" Tree of Twin W. Oak N 80° 45' E. 46.4'
 E-7 Set Conc Mon. 8" ABOVE GR. CHERRY 20" N. 88° 50' E. 42.25' W. OAK 16" N. 89° 30' W. 69.2' W. OAK 24" S 01° 15' E. 85.6
 E-8 Set Conc Mon. 3" ABOVE GR. White Oak 24" S. 40-15 W. 26.62' " " 10" N. 14-30 E. 36.35' " " 36" S 75° E 64.45'

SIGNED BY _____ DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)