

**Barry County Remonumentation Program  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Orangeville Township Quarter Corner 11, 12

<u>Barry</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T2N R10W	K4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on January 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3									
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K4, Post set by US Deputy Surveyor S Sibley in January 1827, witnessed to a White Oak 9, N1-1/2°E, 27 links and a White Oak 14, S33°E, 22 links. In April 1867, County Surveyor AC Willson set a stake and stone by US trees (Liber 2, page 144). In Liber 2, page 146, Willson notes that he set post by bearings. Field notes by Cobb record that he searched for this corner October 15, 1889 and failed to find it. Cobb stated that he measured the mile and set a stake 6 feet east of a Black Oak 8. Cobb stated that he was later told that a crock was buried in place of the original stake. This same note by Cobb also appears in the record for the east quarter corner of Section 12 (M4). A corner record card from the Office of County Surveyor B Reynolds dated February '85 record finding a 2 1/2" axle 3 feet deep and raising it with a 1/2" iron. Witnesses on the card are a quad 12" Oak, N50°W, 52.10; a 12" oak, S35°W, 84.32; a 12" Oak, East, 29.64.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K4, Found 1/2" over 2 1/2" axle and all witness trees from the card. Accepted the axle as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K4, Left axle in place 3 feet deep. Replaced 1/2" rebar with 24" rod with Barry County Remonumentation Program Cap. Rod and cap are 1 foot deep. Witnessed:

- Set nail with Barry County tag in east side quad 12" Oak, N50°W, 52.22
- Set nail with Barry County tag in east side 12" Walnut, S35°W, 84.32
- Set nail with Barry County tag 5' high in 12" Oak, East, 29.61
- Set nail with Barry County tag in E side pole, S10°W, 106.28
- Three feet south of centerline Mullen Road west

Signed by Gary C. Bilow  
Surveyor's Michigan License No. 26453

Date December 30, 1998

