

**Barry County Remonumentation Program  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Orangeville Township Section Corner 11, 12, 13, 14

<u>Barry</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T2N R10W	K5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on January 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5											●		
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K5, Post established in marsh by U.S. Deputy Surveyor S Sibley in January 1827 – accessories a W Oak 7, S 6 W, 238 links and W Oak 9, S 16 E, 175 links. Surveyor J King in Land Corner Recordation Certificates 134 and 164 calls for a steel fence post at the intersection of old fences north and east. King witnesses the post to a 16" twin Oak N 10° W, 158.7 and a 14" Oak N 25° W, 157.3.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K5, Accepted steel "T" fence post as best evidence of the location of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced steel fence post with 1-1/2" x 7' steel pipe with Barry County Remonumentation Program cap projecting 6". Placed steel fence post alongside projecting 4'. Set witness corners on section lines north and east of corner.

Witness Corner 253.17 North  
1/2" rebar with LLS cap 26453  
N58°E 15.22 Spike & tag in S side 10" Oak  
N20°W 21.88 Spike & tag in W side 28" Oak  
S45°W 29.86 Spike & tag in E side 21" Oak  
S50°E 32.60 Spike & tag in W side 12" Oak  
Witness Corner is in old N-S fence (wire down)

Witness Corner 242.30 East  
1/2" rebar with LLS cap 26453  
S30°E 5.22 Spike & tag in 21" Oak  
S80°E 12.59 Spike & tag in 18" Oak  
N5°W 14.32 Spike & tag in 6" Oak, 4' above ground  
S65°W 21.54 Spike & tag in 18" Oak  
Witness Corner is 2' S of old E-W fence (wire down)

Signed by Gary C. Bilow  
Surveyor's Michigan License No. 26453

Date December 30, 1998