

APR 08 1996

COMMISSION

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 20 9 08 AM '95

Sandy Schondelmar
REGISTER OF DEEDS

002328

Register of Deeds Stamp & File Number

For corners in

Barry

(County)

Located in:

Corner Code #/

- | | | |
|------------------------------------|--------------------------|---------------------------|
| 1. Public Land Survey | T <u>2N</u> R <u>10W</u> | A-2 (W $\frac{1}{4}$, 6) |
| | T ___ R ___ | <u>Orangeville Twp.</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on July, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
6	5	4	3	2	1							
7	8	9	10	11	12							
18	17	16	15	14	13							
19	20	21	22	23	24							
30	29	28	27	26	25							
31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

A-2 Not set by GLO
L1, P856 Survey
T iron, May, 1987
PP N 85 E 49.8
4" Poplar N 30 E 86.15
C/L S end 30" CMP N 80 W 40.65'
C/L N end 30" CMP N 45 W 56.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 Found T iron 0.15' E of Township line
PP N 85 E 49.8+

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
AUGUST 14, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 Set Barry Co. Mon. (3/4" x 24" w/Barry Co. Cap) on town line
Nail & Allegan Co. Remon. Tag in N side 10" Willow N 90 W 63.56'
Nail & Allegan Co. Remon. Tag in NW side 16" Poplar N 20 E 90.32'
Nail & Allegan Co. Remon. Tag in NW side 16" Poplar N 25 E 67.97'
PK in SW side PP N 80 E 48.73'
Allegan Co. Mon. E 1/4 Sec. 1, 2-11, North 49.92'
T iron 0.15' E of Mon. set

Signed by John C. Bueche
John C. Bueche

Date Oct 2, 1995

Surveyor's Michigan License No. 13027

