

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SURVEY &
MONUMENTATION

DEC 27 2000

FOR CORNERS IN: BARRY COUNTY
LOCATED IN: T. 2N R. 10W
CORNER CODE # A-3

Seg #2

SECTION

CORNER COMMON TO SECTION 6 & 7
ORANGEVILLE TOWNSHIP



2833

Page: 1 of 2
12/07/1999 08:36A

Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

- 2. Property Controlling in section S.....T.....R.....
- 3. Miscellaneous Property in Sec. S.....T.....R.....
- 4. Lot No.....Recorded Plat.....
- 5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

Nov 8, 1999 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON PER NO. 4 ABOVE AS APPROVED BY BARRY CO. PEER GROUP ON 8-14-95. NO STANDARD BARRY COUNTY REMONIRON OR CAP WAS EVER SET AT APPROVED LOCATION.

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER. THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8-14-95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

- NAIL & TAG IN POWER POLE N30E 90.20'
- NAIL & TAG IN POWER POLE N45W 145.10'
- C/L CABLE BOX N50W 56.00'
- NAIL & TAG IN POWER POLE S50E 83.50'
- C/L ROAD TO WEST NORTH 48.5'+/-
- C/L S ROAD WEST 9'+/-



Raymond Moored

Date *11/24/99*

Surveyors License No. *26463*



2833

Page: 2 of 2
12/07/1999 08:36A

Daria K. Burghdoff- Barry Co. LCRCR

**BARRY COUNTY
ORANGEVILLE TOWNSHIP
T.2N., R.10W.**

A-3

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O., S. SIBLEY, D.S. 1827 (R10W, PG. 97)
WEST 76.96 INTERSECTED W. BOUNDARY 75 SOUTH OF POST
A TAMARACK 10 POST
2. JOHN MERDZINSKI, P.S. L.C.R.C., 5-9-77 NO. 212
SET "T" IRON AT GOVT JOG DIST. FROM NE CORNER, SEC. 12
P. POLE N30E 90.90'
P. POLE N85E 68.73'
P. POLE N45W 14.73'
SE CORNER. SEC. 1, T2N, R11W, NORTH 49.5'
3. COUNTY ROAD COMMISSION
SAME WIT'S AS NO. 2 ABOVE
4. JOHN BUECHE, P.S. L.C.R.C. NO. 2329 REC. 11-20-95
FD. "T" IRON PER NO. 2 ABOVE
C/L COR FENCE POST N10W 147.06'
C/L COR FENCE POST N20W 90.40'
C/L COR FENCE POST N60W 144.88'
C/L GRAVEL ROAD N-S WEST 9'+/-
C/L GRAVEL ROAD WEST, NORTH 50'+/-
NAIL & ALLEGAN CO REMON TAG IN S. SIDE P. POLE N30E 90.91'
ALLEGAN CO. MON. , SE COR 1, 2-11, NORTH 49.48'

SURVEY &
DOCUMENTATION

DEC 27 2000

SECTION