

APR 04 2000

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY

LOCATED IN: T.....2N..... R.....10W.....

CORNER CODE # A-4

1. Public Land Survey

WEST 1/4 CORNER SECTION 7 ORANGEVILLE TOWNSHIP

T..... R.....

T..... R.....

2. Property Controlling in section S.....T.....R.....

S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....



2827
Page: 1 of 1
12/07/1999 09:36A

Darla K. Burghdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	-	-5	-	4	-	-3	-	2	-	-1	-	
3													
4	7	-	9	-	10	-	11	-	12	-			
5													
6	16	-	-17	-	16	-	-15	-	14	-	-13	-	
7													
8	19	-	-20	-	21	-	-22	-	23	-	-24	-	
9													
10	30	-	-29	-	28	-	-27	-	26	-	-25	-	
11													
12	31	-	-32	-	33	-	-34	-	35	-	-36	-	
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O., CORNER NOT SET BY G.L.O.
 - LEE COBB, 1893, (ORANGEVILLE FIELD BOOK, PG. 62)
SET GAS PIPE 4' BY MEASURE
- NO OTHER CORNER HISTORY AVAILABLE.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
Nov 8, 1999 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON AT 39.37' SOUTH OF ALLEGAN CO. CORNER, FITS OCCUPATION LINE TO EAST.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

- SW COR METAL BLDG. N45W 89.20'
- SE COR METAL BLDG. N30W 74.40'
- C/L CABLE BOX WEST 22.40'
- NAIL & TAG IN POWER POLE N45E 44.10'
- ON C/L DRAIN TO EAST
- C/L PATTERSON ROAD WEST 2.5'+/-
- TOP C/L 36" C.M.P. N45W 34.45'

Raymond Moored Date 11/24/99

Surveyors License No. 26463

