

APR 04 2000

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION FOR CORNERS IN: BARRY COUNTY
LOCATED IN: CORNER CODE #
1. Public Land Survey T...2N R...10W ...A-5
SECTION CORNER BETWEEN SECTIONS 7 & 18 ORANGEVILLE TOWNSHIP
2. Property Controlling in section S...T...R...
3. Miscellaneous Property in Sec. S...T...R...
4. Lot No., Recorded Plat
5. Private Claims

Barcode with number 2828
Page: 1 of 1
12/07/1999 08:36A
Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O., S. SIBLEY, D.S. 1827 (R10W, PG. 97) WEST 77.09 INTERSECTED W. BOUNDARY 38 SOUTH OF POST A TAMARACK 6 N35 1/2 W 915 POST
2. COUNTY ROAD COMMISSION STONE AND IRON FOR CORNER ST. SIGN EWE 15.45' SE COR. OF HOUSE NW 77.8' N. POLE OF H. FRAME SE 70.0'
3. CONSUMERS POWER CO. FOUND IRON SE CORNER BUILDING NW 170

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON Nov 8, 1999 BIR BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BAR AT 25.02' SOUTH OF ALLEGAN CO. CORNER. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER. THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-NAIL IN NW SIDE POWER POLE N40E 57.78'
-NAIL IN E SIDE POWER POLE N23W 77.93'
-NAIL IN N SIDE POWER POLE WEST 34.14'
-NAIL IN NE SIDE POWER POLE (N. POLE OF H FRAME) S56E 59.99'
-ALLEGAN COUNTY CORNER ORTH 25.02'
-IN CENTERLINE OF NORTH-SOUTH ROAD

Signature of Raymond Moored Date 11/24/99
Surveyors License No. 26463

