

APR 04 2000

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY

LOCATED IN:

CORNER CODE #

1. Public Land Survey T. 2N R. 10W A-6

WEST 1/4 CORNER SECTION 18 ORANGEVILLE TOWNSHIP T. R. T. R. T. R.

2. Property Controlling in section S. T. R. S. T. R.

3. Miscellaneous Property in Sec. S. T. R.

4. Lot No. Recorded Plat

5. Private Claims

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.



2834 Page: 1 of 2 12/07/1999 08:36A

Darla K. Burghdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

Grid table with columns A-M and rows 2-13. Cell 6A contains a dot and the number 16.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON Nov 8 1999 BR BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BAR PER LCRCS LISTED ABOVE. DURING REMONUMENTATION WORK ALONG LINE FOR ALLEGAN COUNTY, THE EAST 1/4 COR. OF SECTION 13 (M-6) WAS RECOVERED AS ESTABLISHED IN 1928 SURVEY BY COUNTY SURVEYOR MCDUGALL. THAT SURVEY CALLED FOR JOG DISTANCE OF 18.5' PER G.L.O. HOLDING M-6 AND M-7 FOR LINE, A-6 NOW FALLS 1.35' WEST OF RANGE LINE. DUE TO MUCH USAGE OF A-6, THE NORTH-SOUTH POSITION WAS HELD AND A STANDARD BARRY COUNTY MONUMENT WAS SET ON THE RANGE LINE 1.35' EAST OF A-6 AS FOUND.

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP ON RANGE LINE 1.35' EAST OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

- NAIL IN S SIDE POWER POLE WEST 4.71' A-6 AS FOUND WEST 1.35'
-NAIL IN 26" OAK S17E 22.93'
-FD. NAIL (5' HIGH) IN POWER POLE S8W 31.12'
-FD. NAIL (5' HIGH) IN POWER POLE S27W 36.74'
-C/L ROAD TO EAST SOUTH 4'+/-
-C/L ROAD TO NORTH WEST 15'+/-
-M-6, T2N, R11W NORTH 18.10'

Raymond Moored Date 11/24/99

Surveyors License No. 26463



APR 04 2000

SECTION

BARRY COUNTY, ORANGEVILLE TOWNSHIP, T2N, R10W

A-6

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O.
A. NOT SET BY G.L.O.
2. COUNTY ROAD COMMISSION
STA 77 & 76.B FOUND IRON (AT P.1 OF CURVE, NOT IN ROADWAY)
DID NOT DISTURB (SADDLER ROAD NOTES KINGMAN 1992)
3. DONALD A. RATEKIN 5-11-1973 RECORDED L.C.R.C.
1" IRON
14" OAK SSE 22.45'
FENCE CORNER POST SW 31.15'
24" CHINESE ELM NNE 75.0'
4. ROBERT J. JONKER 8-8-1989 RECORDED L.C.R.C.
1" SOLID IRON
SET NAIL-E. SIDE 36" ELM N 15 E 76.0'
FD. SPK. W. SIDE T. POLE S. 30 W 36.09'
FD. SPK. W. SIDE P. POLE S. 15 E 31.27'
GRAVEL ROAD TO NORTH EXTENDED, 15' W
GRAVEL ROAD TO EAST EXTENDED 4' S.
5. DONALD P. RATEKIN, 10-19-1973, ACT 132 SURVEY ,L1.,
P. 137-138



2834

Page: 2 of 2
12/07/1999 08:36A

Darla K. Burghdoff- Barry Co. LCRCR