

APR 04 2000

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FOR CORNERS IN: BARRY COUNTY

LOCATED IN: T. 2N R. 10W CORNER CODE # A-7

1. Public Land Survey

SECTION CORNER COMMON TO SECTIONS 18 & 19 ORANGEVILLE TOWNSHIP

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No., Recorded Plat

5. Private Claims

2835
Page: 1 of 2
12/07/1999 08:36A
Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
Nov 8 1999 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIN IN MON BOX PER NO. 5 LISTED ABOVE. LEFT PIN IN PLACE AND PLACED STANDARD BARRY COUNTY REMONUMENTATION CAP ON TOP OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" IRON PIN WITH STANDARD BARRY COUNTY REMONUMENTATION CAP IN MON BOX

- NAIL IN SE SIDE 6" W. CHERRY S56W 33.43'
- NAIL IN FACE 24" B. WALNUT N2E 43.56'
- NAIL IN NE SIDE 30" OAK N45W 59.00'
- NAIL IN NE SIDE P. POLE S66E 56.66'
- M-7, T2N, R11W NORTH 11.88'
- C/L N&S ROAD EAST 2'+/-
- C/L PVM'T NORTH 10.8'+/-

Raymond Moored Date 11/24/99

Surveyors License No. 26463



