

APR 04 2000

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 2N R. 10W	A-8
WEST 1/4 CORNER, SECTION 19 ORANGEVILLE TOWNSHIP	T. .... R. ....	.....
	T. .... R. ....	.....
	T. .... R. ....	.....
2. Property Controlling in section	S. .... T. .... R. ....	.....
	S. .... T. .... R. ....	.....
3. Miscellaneous Property in Sec.	S. .... T. .... R. ....	.....
4. Lot No. ...., Recorded Plat. ....		
5. Private Claims. ....		



2829  
Page: 1 of 1  
12/07/1999 08:36A

Darla K. Burshdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.  
A. NOT SET BY G.L.O.
- COUNTY SURVEYOR RECORDS  
SET POST A.D. RORK APRIL 2, 1866 (L.2, P. 89)  
SET ON TWP. LINE @ MIDPOINT OF MILE
- ROBERT J. JONKER 8-26-1991 RECORDED L.C.R.C.  
CAPPED REROD ON C/L N-S ROAD ALLEGAN CO.  
CORNER, NORTH 17.59'  
SPK SE SIDE 24" TW. MAPLE N80W 14.80  
SPK S. SIDE 24" OAK N70E 52.48
- DAVID F. PEABODY, RLS# 25866, DECEMBER 16, 1988  
(ACT 132 SURVEY L.1, P.920)

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
NOV 8, 1999 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD PER NO. 3 LISTED ABOVE. REMOVED AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.  
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON \_\_\_\_\_

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD 3/4" X 24" BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL IN POWER POLE N40E 91.70'
- NAIL & TAG IN E SIDE 20" OAK N8W 109.50'
- NAIL & TAG IN SE SIDE 18" MAPLE S45W 117.30'
- NAIL & TAG IN NE SIDE 4" OAK S37E 43.60'
- M-8, T2N, R11W NORTH 17.59'
- C/L N&S ROAD WEST 2'+/-

*Raymond Moored*

Date 11/24/99

Surveyors License No. 26463

