

APR 04 2000

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY
LOCATED IN: T 2N R 10W CORNER CODE # A-9
1. Public Land Survey
SECTION CORNER COMMON TO SECTIONS 19 & 30 ORANGEVILLE TOWNSHIP
2. Property Controlling in section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat
5. Private Claims



2830 Page: 1 of 1 12/07/1999 08:36A

Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

Table with 13 rows and 13 columns (A-M) containing numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O., SYLVESTER SIBLEY, D.S. 1827 (R10W, P.94) A. WEST 77.87 TO A.B. ASH 12 POST ON TOWN LINE B. 25 SOUTH OF POST 16.
2. COUNTY SURVEYOR RECORDS BEARINGS FOUND A.D. RORK APRIL 2, 1866 (L.2, P. 89) FOUND 1 1/2" SOLID IRON 16.58' S. OF ALLEGAN CO. CORNER
3. ROBERT J. JONKER 8-26-1991 RECORDED L.C.R.C. 1 1/2" SOLID IRON CAPPED IRON NORTH 16.58' SPK. NW SIDE 8" BASSWOOD N40E 22.65' SPK. NE SIDE 24" ELM S35E 27.02' STOP SIGN POST WEST 30.60' 16" S OF " T " INTERSECTION

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON Nov 8, 1999 BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" SOLID IRON PER WITNESSES IN NO. 3 ABOVE. REMOVED AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL & TAG IN NE SIDE 8" MAPLE CLUMP N45W 56.80'
-NAIL & TAG IN E SIDE 14" TWIN ASH N11E 84.90'
-NAIL & TAG IN NE SIDE 14" ASH S50E 38.50'
-NAIL & TAG IN W SIDE BASSWOOD CLUMP N80E 22.70'
-M-9, T2N, R11W NORTH 16.50'
-1/2" IRON EAST 33.00'

Raymond Moored Date 11/24/99 Surveyors License No. 26463

