

APR 04 2000

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION
FOR CORNERS IN:
BARRY COUNTY

LOCATED IN: CORNER CODE #

1. Public Land Survey T.....2N R.....10W A-10

WEST 1/4 CORNER,
SECTION 19
ORANGEVILLE TOWNSHIP T..... R.....

2. Property Controlling
in section S.....T.....R.....

3. Miscellaneous
Property in Sec. S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....



2831
Page: 1 of 1
12/07/1999 08:36P

Darla K. Burghdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	-5	4	-3	2	-1							
3													
4	7	-8	9	-10	11	-12							
5													
6	16	-17	16	-15	14	-13							
7													
8	19	-20	21	-22	23	-24							
9													
10	30	-28	28	-27	26	-25							
11													
12	31	-32	33	-34	35	-36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.,
A. NOT SET BY G.L.O.
- COUNTY SURVEYOR RECORDS
STONE FOR POST CORRECTED 40.04 (FROM A-9)
CRESSEY OCT. 9, 1873 (L.1, P.11)
SET 1" IRON 1/2 BETWEEN SW COR & NW COR
- DONALD A. RATEKIN, 4-30-1974 RECORDED L.C.R.C.
1" IRON W END 30" CMP W 23.00'
E END 30" CMP E 27.47'
C/L GRAVEL ROAD E 2'
- DONALD A. RATKIN, RLS# 8781, 11-4-1974,
(ACT 132 SURVEY L.1, P. 264)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
Nov 8, 1999 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON ROD PER NO. 3 & 4 LISTED ABOVE. REMOVED AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD 3/4" X 24" BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- WEST END 30" C.M.P. WEST 23.00'
- EAST END 30" C.M.P. EAST 27.47'
- M-10, T2N, R11W NORTH 19.58'
- C/L N&S ROAD WEST 2.5'+/-
- A-9, T2N, R10W NORTH 2645.31'
- A-11, T2N, R10W SOUTH 2645.08'

Raymond Moored

Date 11/24/99

Surveyors License No. 26463

