

APR 04 2000

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

| | | |
|--|-------------------------|---------------|
| FOR CORNERS IN: BARRY COUNTY | LOCATED IN: | CORNER CODE # |
| 1. Public Land Survey | T. 2N R. 10W | A-11 |
| SECTION CORNER COMMON TO SECTIONS 19 & 30 ORANGEVILLE TOWNSHIP | T. R. | |
| | T. R. | |
| | T. R. | |
| 2. Property Controlling in section | S. T. R. | |
| | S. T. R. | |
| 3. Miscellaneous Property in Sec. | S. T. R. | |
| 4. Lot No., Recorded Plat | | |
| 5. Private Claims | | |



2832
Page: 1 of 1
12/07/1999 08:36A

Darla K. Burghdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 19 | 20 | 21 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O.
A. NOT SET BY G.L.O.
2. COUNTY ROAD COMMISSION
STA 77 & 78.B FOUND IRON (AT P.1 OF CURVE, NOT IN ROADWAY)
DID NOT DISTURB (SADDLER ROAD NOTES KINGMAN 1992)
3. DONALD A. RATEKIN 5-11-1973 RECORDED L.C.R.C.
1" IRON
14" OAK SSE 22.45'
FENCE CORNER POST SW 31.15'
24" CHINESE ELM NNE 75.0'
4. ROBERT J. JONKER 8-8-1988 RECORDED L.C.R.C.
1" SOLID IRON
SET NAIL-E. SIDE 38" ELM N 15 E 78.0'
FD. SPK. W. SIDE T. POLE S. 30 W 38.09'
FD. SPK. W. SIDE P. POLE S. 15 E 31.27'
GRAVEL ROAD TO NORTH EXTENDED, 15' W
GRAVEL ROAD TO EAST EXTENDED 4' S.
5. DONALD A. RATEKIN, 10-19-1973, (ACT 132 SURVEY L.I., P. 137-138)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
Nov 8 1999 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SOLID IRON PER WITNESSES IN NO. 3 ABOVE. REMOVED AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL & TAG IN P. POLE S32E 45.05'
- NAIL & TAG IN P. POLE N51E 82.72'
- NAIL & TAG IN P. POLE N61W 122.05'
- W END 16" C.M.P. N23W 50.54'
- E END 16" C.M.P. N20E 51.80'
- M-11, T2N, R11W NORTH 22.44'
- S. EDGE OF E-W GRAVEL ROAD NORTH 5' +/-
- C/L DITCH TO SOUTH WEST 5' +/-

Raymond Moored Date *11/24/99*

Surveyors License No. *26463*

