

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

MAY 20 2 04 PM '96

Sandy Schwedelmaier

REGISTER OF DEEDS

002374

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 1N R 10W	A-1 NW, 6 PRAIRIEVILLE TWP
	T _____ R _____	
	T _____ R _____	
	T 2N R 10W	A-13 SW, 31 ORANGEVILLE TWP
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, BASIL ANDRESS in a field survey on OCTOBER 14, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O.

SET TWP COR 40 LKS S OF TEMP. POST
W. OAK 9 N 44 1/2° W 29
B. OAK 12 S 65° E 17

CONT. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 2" TILE W/ ROCKS AROUND IT.
TWIN OAK W 41.0'±
16" OAK S 10° E 9.5'±
DIST S TO M-2 2623.75'
DIST W TO L-1 2641.01'
SET STD. ALLEGAN CO. MON. IN CENTER OF TILE

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

Nov 13 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. ALLEGAN CO. MON. (3/4" X 36" IRON W/ CAP) IN 2" TILE W/ STONES AROUND IT.
16d & REMON. TAG W. SDE 16" OAK S 10° E 9.53'
16d & REMON. TAG N.E. SDE 12" OAK S 55° E 25.29'
16d & REMON. TAG S. SDE 14" OAK N 85° E 27.70'
16d & REMON. TAG W. SDE 22" MAPLE N 15° E 47.44'
16d & REMON. TAG N. SDE 10" MAPLE N 75° W 41.92'
16d & REMON. TAG N.W. SDE 6" MAPLE S 60° W 30.54'
IN LINE W/ OLD DOWN FE TO EAST



Signed by Basil Andress

Date 3-1-96

Surveyor's Michigan License No. 30075

CONTINUED FROM FRONT OF CERTIFICATE

2374-A

3967-5

A. DESCRIPTION OF . . . SUBSEQUENT RESTORATION

CRESSY, BARRY CO. SURVEYOR 1884
FD OLD BEARINGS & POST SET TILE
W. OAK 12 N 41½° W 19½'
W. OAK 14 N 22° E 17'

OLD ALLGAN COUNTY SURVEYOR'S NOTES
2" TILE W/ ROCKS AROUND IT
TWIN OAK W 41.0'
12" SOFT MAPLE NW 16.2'

D.A. RATEKIN, C.S. 1971
DIST S TO M-2 2623.82'
DIST W TO L-1 2642.29'

L.C.R.C. L-1, P-193 4-18-72
2" TILE W/ ROCKS AROUND IT
30" MAPLE N 50° W 15.6'
40" TWIN OAK W 41.0'
20" MAPLE S 15° E 9.4'

SURVEY &
REMONUMENTATION

MAY 20 1997

COMMISSION

